SCIENTIFIC AMERICAN

[Entered at the Post Office of New York, N. Y., as Second Class Matter. Copyright, 1901, by Munn & Co.]

A WEEKLY JOURNAL OF PRACTICAL INFORMATION, ART, SCIENCE, MECHANICS, CHEMISTRY, AND MANUFACTURES.

Vol. LXXXIV.—No. 24.
ESTABLISHED 1845.

NEW YORK, JUNE 15, 1901.

$3.00 A YEAR.
8 CENTS A COPY.



View of East River Bridge from Brooklyn, Showing Temporary Footway Cables.



Roadway. Bicycle track. Footway. Surface cars. Elevated cars. Footway. Bicycle track. Surface cars. Roadway.

Extreme Breadth, 118 Feet. Depth of Trusses, 40 Feet. Length of Main Span, 1,600 Feet.

THE FLOOR-SYSTEM OF THE NEW EAST RIVER BRIDGE.—[See page 374.]

© 1901 SCIENTIFIC AMERICAN, INC.



Scientific American.

ESTABLISHED 1845

MUNN & CO., - - - EDITORS AND PROPRIETORS.

PUBLISHED WEEKLY AT

No. 361 BROADWAY, - - NEW YORK.

TERMS TO SUBSCRIBERS

One copy, one year, for the United States, Canada, or Mexico $3.00
One copy, one year, to any foreign country, postage prepaid. £0 16s. 5d. 4.00

THE SCIENTIFIC AMERICAN PUBLICATIONS.

Scientific American (Established 1845)..... $3.00 a year
Scientific American Supplement (Established 1876) ..... 5.00 "
Scientific American Building Edition (Established 1885). ..... 2.50 "
Scientific American Export Edition (Established 1878)..... 5.00 "

The combined subscription rates and rates to foreign countries will be furnished upon application.
Remit by postal or express money order, or by bank draft or check.
MUNN & CO., 361 Broadway, corner Franklin Street, New York.

NEW YORK, SATURDAY, JUNE 15, 1901.

The Editor is always glad to receive for examination illustrated articles on subjects of timely interest. If the photographs are *sharp*, the articles *short*, and the facts *authentic*, the contributions will receive special attention. Accepted articles will be paid for at regular space rate.

THE GREATEST OF POWER STATIONS.

Undoubtedly the most interesting electrical installation now being carried out is the equipment of the Manhattan Elevated roads with electricity. The great power house, two hundred feet in width by four hundred feet in length, will be the largest in existence, and its compound engines will, we believe, without exception, be the largest single steam units to be found anywhere in service on land. The normal capacity of the power station will be 65,000 horse power, and the maximum capacity about 100,000 horse power. The steam plant will be made up of eight compound engines, which will be capable of running under a continuous load of 12,000 horse power each. These engines are of an entirely new type, and they are placed in pairs on each end of a shaft which carries a Westinghouse generator with a revolving field 32 feet in diameter and weighing 185 tons. The chief novelty of the engines consists in the fact that the high and low pressure cylinders are placed at ninety degrees, the high-pressure being horizontal and the low-pressure vertical. As there are two engines to each shaft, the turning moment is perfectly even, so much so that the customary flywheel is dispensed with, its place being taken by the heavy revolving field of the generator. The high-pressure cylinders are 44 inches and the low-pressure cylinders 60 inches in diameter, the common stroke being 88 inches. To find engines that will compare with these in size, we must refer to the engine rooms of some of the largest ocean steamships. The most powerful marine engines are those of the "Deutschland;" each quadruple expansion engine on this ship has indicated in twenty-four hours as high as 18,500 horse power, or 50 per cent more than the maximum capacity of the engines above described.

A COSTLY EQUIPMENT.

Apropos of the new power station of the Manhattan Railway Company, it is of interest to note that the mere electrical equipment of the rolling stock will cost just $3,000,000. Hitherto the motive power on the elevated system has been furnished entirely by steam locomotives, and the trains on the most important lines have averaged, during the rush hours, five cars in length. Under the new system the average length of the trains will be six cars, of which the leading and trailing cars will be equipped with motors. The General Electric system of train control will be used, the motor circuits on the motor cars being opened and closed by magnets which are themselves actuated by a train circuit under the direct control of the motorman. The electrically equipped experimental train, recently described in this journal, is running steadily on the Second Avenue line in this city, and valuable data as to cost of operation, etc., are being thereby secured.

RAPID TRANSIT TUNNEL TO BROOKLYN ASSURED.

Although the temporary delay to which the Rapid Transit Tunnel from New York to Brooklyn has been subjected by obstructionist tactics on the part of certain members of the Municipal Assembly of Brooklyn has been vexatious, it has served the good purpose of drawing forth from President Orr a masterly defense of the conduct of the affairs of the road by the Commission over which he presides. There is no question that President Orr's vindication will receive the unanimous approval of the citizens of Greater New York. It will be two or three months before the final survey of the tunnel is completed and the plans drawn up, but there is no reason why work should not be under full swing during the fall of this year. Without the Brooklyn tunnel the scheme would have been incomplete; but with this connection we may look for the time when the Brooklyn half of the Rapid Transit scheme will be as extensive as that in Manhattan Island, and only second to it in the density of its traffic.

THE WAVE LINE OF THE "GEORGIA."

As the result of a slight error in the numbering of the official plans which were furnished us from the Navy Department, Washington, the titles to the photographs showing the wave line of the model of the "Georgia," which were reproduced in our recent article on the model basin at Washington, are reversed. The wave line which is credited to a speed of 27½ knots actually accompanies a speed of 19 knots, and vice versa. The height and bulk of the bow wave vary, of course, with the speed, and are greater as the speed increases. In connection with these photographs, we would draw attention to the fact that the enormous piling up of water around the bow of the model at the higher speed affords a graphic evidence of the fact that the resistance to a vessel (and therefore the horse power required to drive her) increases as something more than the cube of the speed. Although surface or skin friction accounts for some of the ship's resistance, it is chiefly the displacement of the surface water in a vertical direction—the continual lifting of so much dead weight through such a height in such a time—that calls for rapidly-increasing expenditures of power at the higher speeds.

GERMANY'S FOREIGN TRADE IN MACHINERY.

The returns of the foreign trade of Germany for the year 1900, recently published, acquire particular interest from the fact that for the first time the imports and exports of machinery have been specialized. The total imports of this kind amounted to $18,639,360, an increase of $3,109,000 over the value of machinery imports in 1899. The value of the exports of machinery was $42,776,000, an increase of $500,000 during the year. As the statistics show the proportion of the import trade in machinery that comes from this country, we commend them to the attention of our manufacturers, as indicating the lines along which their efforts might be profitably expended in increasing our imports into Germany of articles which are now supplied almost exclusively by other countries. It is not surprising to learn that out of a total importation of 28,825 tons of agricultural machinery, over 20,000 tons came from the United States. Great Britain supplied a little over 5,000 tons, and the remainder was imported in relatively small amounts from half a dozen other European countries. The second largest item in the list is that of cotton spinning machinery, the imports of which amounted to 10,863 tons. As regards this commodity the conditions are entirely reversed, Great Britain contributing 9,876 tons and the United States nothing at all. Here, surely, is an industry to which our manufacturers might well turn their attention. The demand for cotton-spinning machinery is increasing rapidly all over the world, and many countries, such as Egypt, Turkey, Bulgaria and Greece, which up to the present time have imported large quantities of cotton goods, are now making a determined effort to establish cotton industries of their own. There is also a demand for cotton-spinning machinery in South America and the far East. The manufacture of cotton machinery seems to be to-day in a somewhat similar position to the tin-plate industry fifteen years ago. That is to say, it is practically non-existent, at least so far as the export trade is concerned. There is, of course, some exporting of cotton-spinning machinery to South America, but the sum total of our export trade in this most important branch of machinery is not at all commensurate with our exports in other branches of machinery. The statistics indicate that European countries place a high value upon the possibilities of foreign trade in this line, and consider that successful competition with Great Britain is quite feasible. Germany herself exported over four and a half million marks' worth of cotton-spinning machinery in the year 1900.

The imports of machine tools into Germany amounted to 6,270 tons, of which 4,757 tons came from the United States; but out of a total importation of 4,308 tons of locomotives and locomobiles our share amounted to only 189 tons, as against 3,196 tons (chiefly portable engines for agricultural work) imported from Great Britain. There is no doubt that the latter country excels in the manufacture of these engines; but there is nothing in the nature of the case to prevent the United States from supplying an agricultural portable engine which will be just as serviceable in its way as the agricultural machinery, in the manufacture and export of which this country is pre-eminent. Another item to which we would direct the attention of our manufacturers is that of electrical machinery, the imports of which into Germany amounted in 1900 to 4,350 tons, of which we contributed only 343 tons, as against an importation from Austria-Hungary of 2,080 tons and from Switzerland of 977 tons. We have already in these columns directed attention to the valuable work which the Budapest engineers are doing in the electrical field. Although our electrical exports to Great Britain and elsewhere are valuable and growing, it behooves our electrical manufacturers to study the possibilities of the Ganz high-pressure alternating system, which, it will be remembered, was at first adopted on its merits by the London underground roads in preference to the direct system, and was only finally rejected after a vote of a majority had been secured by those interested in the installation of the latter type.

Another export to which we might profitably turn our attention is that of weaving machinery Out of a total of 8,184 tons, 6,138 tons were imported into Germany from Great Britain, 1,420 tons from Switzerland and nothing from this country. Summarizing the imports of lesser accounts: out of a total importation of 4,365 tons of steam engines, 1,738 tons came from Switzerland, 1,061 from Great Britain and 200 tons from the United States. Of 1,666 tons of lifting machinery, 574 tons were contributed by this country; of 1,055 tons of flour-milling machinery, 182 tons were contributed by the United States; while of 473 tons of rolling mill machinery, 77 tons came from this country.

An examination of the list of exports from Germany of machinery shows that Russia is by far the largest buyer of German goods. Thus of nineteen and a half million marks' worth of sewing machines, Russia was by far the largest buyer, as she was also of locomotives and portable engines, taking 4,024 tons out of a total export of 12,293 tons. Of 21,555 tons of steam engines, Russia purchased 5,586 tons and France 4,247 tons. The total export of electric machinery was about 13,000 tons, of which Russia again was the largest buyer, taking a total of 3,077 tons. Russia was also the largest buyer of agricultural machinery from Germany, taking about half of a total export of 13,000 tons. The exports of machine tools from Germany amounted to 9,267 tons, of which Russia purchased 2,370 tons and Austria Hungary 1,236 tons. The full figures of Germany's machinery trade are given in an article in the current issue of the SUPPLEMENT, which we commend to the careful reading of our manufacturers in the special lines to which reference has been made above.

LAWS OF ABSORPTION OF X-RAYS FOR DIFFERENT BODIES.

M. Louis Benoist has lately made a series of experiments at the physical laboratory of the Sorbonne concerning the transparence of different bodies for X-rays. In a former series of experiments he showed that these rays are not homogenous and undergo a selective absorption by the different bodies traversed. In studying a certain number of bodies it appeared that the transparence to X-rays is not entirely a function of the mass, but that the absorbent power, or *specific opacity*, increases in general with the density. He showed also that different bodies possess a property which may be called radiochroism, as it is comparable with the coloration of substances which are transparent to light, and in virtue of which the relative opacity of two bodies changes with the mass traversed and with the nature of the X-rays used, the most rapid change taking place with the denser bodies. In continuing these researches he has studied about 120 different bodies, simple and compound, and has obtained results which enable him to deduce the principal laws of transparence of matter for X-rays. A prism of paraffin, 2-5 inch square at the base, and 3 inches long, is taken as a standard; its absorption for X-rays of a determined character is measured, and the absorption of other bodies compared with it by finding the length of a prism of the same base which will give the same absorption as the standard; the mass of this prism thus determines the *equivalent of transparence* of the body. This equivalence permits of calculating the mean specific opacity of the body for the thickness corresponding to that of the standard. The measurement of these equivalents brings out some interesting results, of which the principal are as follows: First, the specific opacity of a body appears to be independent of its physical state; for instance, it is the same for water and ice, it is independent of temperature, etc. Second, the specific opacity seems to be independent of the mode of atomic grouping of the body, that is, of crystalline forms, allotropic states, etc. (allowing for differences of purity); it is the same, for instance, for anhydrous alumina and corundum, for the different forms of carbon, crystalline and amorphous, for yellow and red phosphorus, etc., also for isomeric organic compounds. Third, it appears to be independent of the state of freedom of the atoms, and the equivalent of transparence of a mixture or combination may be calculated from those of the elements which compose it (taking account of possible difference of radiochroism); thus for silicon the equivalent measures 15.7, and for oxygen 44.5, from which that of quartz is calculated at 24, corresponding to the measured value, 24.1. In another case, caustic lithia measures 57 and oxygen 44.5, giving for lithia a calculated value of 113.8, the measured value being 115. The specific opacity for X-rays, measured under determined conditions, may be considered as a prop-

© 1901 SCIENTIFIC AMERICAN, INC.

erty of bodies allied to that of atomic weight, atomic calorific capacity, etc. As it depends entirely upon the nature of the atoms, the experimenter sought a relation between it and the atomic weights of different bodies, and plots a curve which is quite regular, having somewhat the form of a hyperbola. This curve may be modified by varying the conditions of the experiment, which may be done in three different ways. First, by modifying the character of the X-ray tube; second, by changing the thickness of the standard, which causes, for the different bodies, a variation corresponding to their mass, and in consequence a more or less complete selection of the rays; third, by placing screens of different character in the path of the rays. A series of curves is thus obtained, varying with each experiment. By interposing various screens in the path of the rays, those of greater penetrative power may be sifted out, and it appears that these rays show nearly a direct proportionality between the specific opacity and atomic weight.

EXPECTED RETURN OF ENCKE'S COMET.

BY M. PROCTOR.

Among the periodic comets due in 1901 is Encke's comet, which is expected to return to perihelion about the middle of September. Its last return to perihelion took place on May 24, 1898, the same day on which it also occurred at the first predicted return in 1822. The prediction was made by Johann Franz Encke (after whom the comet has been named), and he detected the periodicity of the comet in 1819.

The comet had been frequently observed during the preceding fifty years, and as soon as the elements of its orbit had been computed and compared with the elements of the orbits of comets which had previously appeared, it was found to be the same comet which had been observed in 1786, 1795 and 1805. Having thus identified the comet at four different returns to perihelion, Encke was enabled to ascertain the period of its revolution with great precision, the result being 3½ years, the comet having the shortest known time of revolution and being the first of the short-period comets.

Encke predicted its return for 1822, making due allowance for planetary perturbations, and on account of its position in the heavens, he announced that the comet would only be visible in the southern heavens. The return of the comet was therefore looked for by astronomers living in that part of the world, and during the month of June was sighted by Rumker at Parramatta, in New South Wales. The next return was predicted to take place in 1825, and on the 13th of July—true to its appointed time—the comet was observed by Valz at Nismes.

The next return took place in 1828, when it was first seen by Struve, at Dorpat, in Russia, on the 13th of October of that year, and remained under observation at the European observatories until December 25. On November 7, 1828, Prof. Struve made a series of observations of the comet, and he noticed a star of the eleventh magnitude so near the center of brightness in the comet that he mistook it at first for the nucleus. The brightness of the star was not in the least perceptible degree diminished by the mass of cometary matter through which its light had passed. By November 30 the comet had greatly increased in brightness, and this must be ascribed to the contraction and consequent condensation of the nebulous matter of which it is composed, as it receded from the sun.

In 1832 the comet again returned to its perihelion, but being unfavorably situated for observation, it was only seen by Harding, at Göttingen, on the 21st of August. However, it was observed by Henderson, at the Cape of Good Hope, during the entire month of June, and was also seen at Buenos Ayres. In 1835 it was observed from July 22 till August 6, and in 1838 it was seen at Breslau on the 14th of August as a very faint, ill-defined object. It subsequently increased in brilliancy and continued visible until the middle of December.

In combining all the observations which had been made from 1786 to 1838 inclusive, Encke found that the period of revolution of the comet was regularly diminishing by about 2½ hours at each return to perihelion. This effect he attributed to the retarding action of a resisting medium in space. This theory seemed to be confirmed by observations made at the return of the comet in 1842, 1848, 1852, 1855, 1858, 1862 and up to 1868; but at its return in 1868 the acceleration had fallen to one-half its customary and, until then, constant value. The change has proved permanent, and accumulated facts bid fair to banish the theory of a "resisting medium" out of existence.

The comet has been seen at every return to perihelion lately, the dates of its visits being 1895, 1898, and it is now looked for in 1901. It has been described as irregular in form and "lumpy" in appearance, seldom showing a well-defined nucleus. Under very favorable circumstances it can be seen with the unaided eye, but is usually visible only in the telescope. It does not exhibit much in the way of jets and envelopes, and the train, when visible, is but a degree or two in length. As the comet approaches the sun, a peculiar contraction takes place in its volume, while it resumes its original dimensions when receding from the sun. For instance, at a distance of 130,000,000 miles from the sun, it has a diameter of nearly 300,000 miles, but when it is near perihelion (at a distance from the sun of only 33,000,000 miles), its diameter shrinks to 12,000 or 14,000 miles, the volume then being less than one-ten-thousandth of what it was when first seen.

According to Sir John Herschel, the explanation of this peculiar contraction in Encke's comet is optical rather than real, "that near the sun a part of the cometary matter becomes invisible, having been *evaporated*, perhaps, by the solar heat, just as a cloud of fog might be."

THE ST. LOUIS EXPOSITION OF 1903.

The preliminary work is progressing with much vigor at St. Louis for the Louisiana Purchase Exposition, and the current month will show the selection of a site for the Exposition. The organization is proceeding with the fully formed purpose of having the Exposition open on May 1, 1903. We are informed by the Secretary, Mr. W. B. Stevens, that work begins with a capital of $15,000,000, fully secured. In June, 1900, Congress made a part of the Sundry Civil Bill a section pledging an appropriation of $5,000,000 to the Exposition, if the organization of St. Louis should show, to the satisfaction of the Secretary of the Treasury, $5,000,000 raised by popular subscription and $5,000,000 of bonds voted by the city of St. Louis. At the following election in Missouri, November, 1900, the Constitution of the State was amended not only to permit the city of St. Louis to issue $5,000,000 in bonds, but also to authorize an appropriation of $1,000,000 by the State for its own participation in the Exposition. Since that election, the Legislature has carried out its part by making the appropriation of $1,000,000. The Municipal Assembly has by ordinance authorized the issue of bonds, and the people of St. Louis have subscribed for over $5,000,000 of stock. In February of this year, the Secretary of the Treasury was furnished with the evidence that subscriptions for the full amount stipulated by Congress had been secured, and that the bonds had been legally authorized. He certified these facts to Congress. A special committee reported the bill providing for an appropriation of $5,000,000, and the House passed it by more than a two-thirds vote. The action of Congress in appropriating $5,000,000 to the Exposition, making the government a financial partner to the extent of one-third, constituted the most notable provision yet made in the history of exposition legislation. President McKinley has appointed a government commission, and the first meeting has been held in St. Louis.

Those who have visited the Pan-American Exposition at Buffalo have admired the splendid arrangement, the architecture, the landscape gardening and the lighting. It is a triumph and exceeds any other Exposition in beauty. All this was accomplished with $5,800,000 capital and appropriations. With such a sum as $15,000,000 there is no question that St. Louis can give the most artistic though not the largest exposition ever held.

TWENTY-FIVE KNOT NAVAL SCOUTS.

At the Annual Conference of the Institution of Naval Architects in London, Rear Admiral C. C. P. Fitzgerald outlined a scheme he has had formulated for scout vessels of high speed and good seagoing qualities. His idea is by no means original, for the French government some two years ago sanctioned the construction of two such vessels for the purposes advocated by Rear Admiral Fitzgerald, although so far they have not been constructed. The vessel suggested by this officer would be a twin-screw steamer 400 feet in length, with a beam of 44 feet, 3,800 tonnage, draught 14 feet, 17,000 horse power, and a continuous ocean speed of 23 knots, rising, if the exigencies demanded it, to 25 knots per hour, a bunker capacity of 1,200 tons, and a normal supply of 500 tons of coal. She would be provided with a protective deck 2 inches thick on the slope, and would carry six 4-inch guns, with twelve machine guns. Although not intended for fighting purposes, she would yet be capable of defending herself against torpedo attack. The radius of action of this scout would be 1,500 miles at 25 knots, 2,000 miles at 23 knots, 3,000 miles at 18 knots, and 8,500 miles at from 10 to 15 knots. The maximum speed would enable her to escape from first-class cruisers. Her estimated cost would be $1,350,000. Commander Clover, of the United States Navy, who entered into the discussion, remarked that in the Spanish-American war the Americans employed liners such as the "New York" and "St. Paul" for this class of work, and they were found to fulfill all the necessary requisites, either as dispatch or scouting vessels. The result of their experience had convinced them that it was undesirable to construct special vessels as scouts, since in order to be efficient the vessels would have to be of large dimensions, so that high speed might be maintained at sea at all times.

SCIENCE NOTES.

The excavations in Carthage are producing excellent results. The Punic necropolis near the altar of St. Monica, at Carthage, has resulted in the finding of painted terra cottas, censers, figurines of women, bronze razors and engraved inscriptions of human beings, birds, etc., amulets of gold, silver and ivory.

The eminent French chemist, M. Armand Gautier, has reported a discovery to the Paris Academy of Sciences which may prove of great hygienic value. He has found that finely powdered volcanic stones, treated by boiling in water at a temperature of 250° to 300° Celsius, yield a liquid identical in composition with the ordinary sulphur water of mineral springs, except that it is stronger than the latter.

Dr. Harlow Brooks has been appointed pathologist to the New York Zoological Park. The animals furnish a splendid field for the study of comparative pathology. A laboratory will be fitted up for Dr. Brooks' use. He will make regular visits to the park to examine into the hygienic conditions of the animals and recommend such treatment, and to make such autopsies and microscopic studies as will tend to advance our knowledge of the prevention and treatment of diseases peculiar to animals.

Celluloid has always been manufactured by dissolving nitrocellulose in camphor—that is to say, forming a mixture of nitrocellulose, camphor and alcohol. But there are other ways of mixing it. According to a publication of the Société Générale pour la fabrication des matières plastiques de Paris, celluloid can be made by using naphthalene instead of camphor. The celluloid thus produced, the paper adds, is just as good as, if not better than, that in which camphor forms one of the ingredients.

The Surgeon-General of the United States Army has approved the report of a special medical board by which the conclusion was reached that the mosquito is responsible for the transmission of yellow fever, and the medical department of the army is moving energetically to put into practical operation the methods of treatment for prevention of yellow fever, involving a radical reversal of the existing methods, which form the basis of the report. The liberal use of coal oil to prevent the hatching of mosquito eggs is recommended.

German papers report that an Englishman, Mr. H. Houbon, has invented a process for making very pure hydrogen from acetylene. He condenses acetylene in a Cailletet steel bomb up to 5 atmospheres, and ignites it by means of electricity. Hydrogen and carbon are formed; the latter precipitates in the form of fine soot. The process is without danger and makes it possible to generate hydrogen on a large scale very cheaply. This invention may mean much for balloon technics, as the present methods of making hydrogen are expensive.

Prof. Dr. Voges, the director of the National Board of Health at Buenos Ayres, according to German papers, has found a remedy for mosquito bites. He states that he discovered it by accident during his trip to Paraguay to study the pest. He had been supplied with all sorts of remedies, among them naphthalene, an article of no value whatever against the pest; but on using it for mosquito bites, he found it of surprising effect. It neutralizes the poison, even when the spot bitten is greatly inflamed. If fresh bites are rubbed with naphthalene, no swelling follows. The professor considers naphthalene almost a specific against mosquito poison.

The State of California has appropriated $250,000 to purchase and preserve the grove of redwoods near Santa Cruz. This excellent work was accomplished largely through the agency of a body of Californians especially organized for the purpose, called the Sempervirens Society. The area purchased is unfortunately not very large, and the finest redwoods are found further north. Several thousand acres of land will be purchased in the neighborhood of Humboldt Bay, running from the ocean back across the summit of the coast range. Two or three millions of dollars would be sufficient to make the entire purchase, and the government would do well to preserve this wonderful collection of forest trees for all time.

The heavy yoke of paternalism weighs on the pharmacists in Germany, says The American Druggist. Every detail of the practice of pharmacy is closely supervised by the government. No smoking, no loud and unnecessary conversation are allowed in stores and no domestic animal can be tolerated in them. The pharmacists are being gradually replaced by the "drogisten," who are only permitted to sell the simpler drugs and medical supplies, but cannot dispense prescriptions, and can only sell poisons under special restrictions for household use. Licensed pharmacists are required to be present in their stores from six A. M. to ten P. M., and during the night must be at all times ready to respond to the call of the applicant for even trifling amounts of drugs.

© 1901 SCIENTIFIC AMERICAN, INC.

THE STEAM YACHT "LYSISTRATA."

The "Lysistrata" has the following dimensions: 285 feet load water line; breadth, molded, 39 feet 9 inches; depth, 24 feet to the main deck. She was designed by George L. Watson, and the decidedly unprepossessing look of the ship conveys the impression that the famous designer, whose yachts are renowned for their beauty, has had to work under unusual limitations. Mr. James Gordon Bennett, the owner, holds a master's certificate, and is supposed to be something of a critic of yacht design and yacht construction. If it was his aim to secure originality, it will be conceded that he has made a striking success.

Yacht designing has of recent years run more and more in the direction of flowing curves and beautiful outlines. Clipper bows of long overhang and graceful curves, low waists with great spring in the sheer, and masts and funnel set at a considerable rake, have all been combined to beautify the models, with the result that the best of the modern yachts are undeniably graceful and pleasing. In "Lysistrata," however, the curving clipper bow has been discarded in favor of a straight stem, the sheer gives but a moderate rise fore and aft, the counter is long and looks longer through the absence of forward overhang; for spars there is only one mast perched abaft the funnel and a single yard, to be used for signaling purposes, and mast and funnel are set apparently plumb; though they have in reality rake enough to keep them from looking as if they were falling forward. The whole effect is odd and disappointing, though the result is said to be better in the actual vessel than in the illustration. In any case we sincerely hope that the "Lysistrata" will never be accepted as a model for our steam yachts; for we should be sorry to see the oddities which have been incorporated in this vessel repeated. The single mast with its yard and the general appearance of the bow are strongly suggestive of the yachts which were purchased by the navy during the Spanish war and transformed into scouts and lookout vessels. There were good reasons for the changes made; but it was the universal opinion that the beauty of the transformed yachts was almost entirely lost by the time they were in fighting trim. We fail to see any good reason why changes in yacht architecture which were due to the necessities of war should be perpetuated in time of peace.

The hull is of steel, and built to Lloyd's highest requirements, 100 A 1, under special survey. A double cellular bottom runs the whole length of the ship, and is divided into water-tight compartments so that it may be utilized for the carrying of water ballast. Over the hold there are five decks, and notwithstanding the exceptional amount of space given up to the boilers and engines the hull is made to provide ample accommodation for the owner, his guests, and the large staff required for the proper working of the ship.

Amidships a considerable amount of accommodation is given up to the casing of the boiler and engines, and here there is a novelty which should appeal strongly to those of the guests who desire to see more of the working of the ship than generally comes under the notice of the yachting guest. Under the main deck and above the engines there is a large open well. Round this is a spacious railed gallery from which the whole work of driving the ship can be studied. Aft of this there are more staterooms and stairways giving access to the lower decks. The main deck is finished with a full poop, and a low turtleback forecastle, and it must be admitted that the whole sweep presents an effect free from any suggestion of topheaviness or overloading. On the cabin deck the chief feature is the owner's principal stateroom, which is a specially spacious apartment measuring no less than 20 feet square. Forward of this there are four suites of staterooms, dressing-rooms, and bathrooms, all of them planned on a much roomier scale than is usually seen aboard ship. The lower decks are given up principally to the storerooms, though accommodation is found here for a few servants and crew.

The engines are triple expansion, in two sets, each with high-pressure, intermediate, and two low-pressure cylinders. They run with the utmost smoothness, and it was remarked in the course of the trials that it was almost impossible, in some parts of the ship, to tell when the engines had started. There are five boilers of the ordinary Scotch type, four being used for feeding the principal engines, while the other is used for the various auxiliary engines. No statement has been made as to the speed contracted for, but the trials were particularly thorough and exhaustive. Three full speed runs at full power were made between Cloch and Cumbrae, and the average speed obtained was 19.27 knots.

"Lysistrata" carries eight boats, three of them being steam launches, and the other five intended for propulsion by oars and sails. She has been provided with a very complete set of auxiliary engines, and is lit throughout by electricity. Practically the only concession to the custom of external decoration is in the immense owl carried as figurehead, and fitted in such a way that the eyes can be made to blaze with electric searchlights. From either side runs a scroll of carving, into which there has been wrought the owner's motto, "La nuit porte conseil."



STEAM YACHT "LYSISTRATA."

Length, 285 feet. **Beam,** 39 feet 9 inches. **Depth,** 24 feet. **Speed,** 19.27 knots.

Theodosius F. Secor died recently, at the advanced age of ninety-two. He was one time a partner of the late Commodore Cornelius Vanderbilt, and was a pioneer marine engine builder. In 1848 he built the steamship "New World," which at that time was the fastest and largest vessel in this country. It was not until nearly thirty years later that a vessel with equal speed was built. Mr. Secor also built many of the Hudson River boats, as well as some for the Great Lakes.

AN EFFICIENT CAR-FENDER.

A life-guard which has successfully withstood the most severe tests to which it could be subjected on Canadian electric cars running at high speed is the subject of the illustration herewith reproduced. For the photographs from which these illustrations were made we are indebted to the inventor, Mr. William T. Watson, of Victoria, B. C.

The car-fender is composed of front and rear beds supported by a frame consisting of a relatively stationary rear section and a front section mounted to slide to and from the rear section. The rear bed is inclined; its upper end is attached to the car, while its lower end is located above the rear frame-section. To the lower end of this rear fender-bed, the front bed is hinged by its rear end. The front end of the front bed is attached to the sliding section of the frame.

The frame is supported by a transverse shaft mounted in brackets extending downward from the car. The transverse shaft is provided with upwardly-projecting arms located in the path of push-bars mounted to slide longitudinally beneath the car and connected with a spring-pressed rock-shaft. With this rock-shaft a rack-bar is connected, extending through the platform of the car. A holding-pawl is provided to lock the rack-bar. The rack-bar is operated by a foot-lever to throw the fender into operative position.

The two beds of the fender are yielding; and the force of a shock is still further broken by a rubber buffer on the front bed and by the fact that the front bed can slide back. In case of an emergency the gripman or motorman depresses the foot-lever which lifts the rack-bar, the holding-pawl engaging the teeth as they ascend through the platform and preventing the fender from rising. The push-bars beneath the car-bottom press outward on the upwardly-extending arms of the transverse shaft, causing the fender to drop at the front end. When the fender is to be raised back to its initial position, the holding-pawl is released from the rack-bar, the rock-shaft being turned by its spring. The fender can therefore be adjusted any desired height from the rails and locked against rising, but is not prevented from dropping from its own accord if any obstacle fall upon it.

The fender can be raised to any desired height while the car is running at full speed. Such is the mounting of the frame, that the entire fender can be removed with astonishing quickness. The fender can be applied to any car and operated from any point on the car. No time is lost at the end of a trip in adjusting the fender, for the motorman has only to operate his foot-lever.



Fender Completely Removed from Car.



Car-Fender in Operative Position.



Fender Raised.

VIEWS OF THE WATSON LIFE-GUARD.

Cement for South Africa.

Consul-General Guenther writes from Frankfort, April 15, 1901: According to official reports, South Africa is a good market for cement. All public buildings, stores, and dwellings are coated with cement. There are very few wooden buildings erected. The masons in South Africa are mostly Malays. They are skilled in their trade and do the work very neatly. Cement is also largely used in the construction of aqueducts, wharves, chimneys, walls, etc. While the principal import of cement is from Great Britain, considerable quantities are also imported from Belgium and Germany, the latter, on account of its cheapness, increasing. Belgium cement is of good quality and as cheap as the English article. The reports state that American cement could compete well, as transportation from our country is not higher than from Europe. Cement cannot be made in South Africa, for lack of raw material.

Minnesota State Legislature, in its last session, enacted a law that money may be loaned to fireproof grain elevators without insurance. The elevators must be passed upon as fireproof by the State Railway Commission.

© 1901 SCIENTIFIC AMERICAN, INC.

THE ELECTROGRAPH—A NEW FACSIMILE TELEGRAPH.

Facsimile telegraphs are by no means new. Pictures, handwriting and printed matter have often enough been electrically transmitted from one station and accurately reproduced at a second. But the instruments whereby the transmission and reception of a character or sign is effected have not been noteworthy for their simplicity or for their speed. Moreover, it is usually necessary to employ, either at the transmitting end or at the receiving end of the line, chemically-prepared paper or tissue to receive the pictorial message. A reproduction thus made cannot be photo-engraved clearly, hence is not practical for newspaper work. Among the inventions exhibited by the United States Patent Office at the Pan-American Exposition may be found a facsimile telegraph which certainly marks a noteworthy advance in the art of transmitting pictures electrically, and shows no little ingenuity on the part of its inventors in endeavoring to overcome the objections which we have cited. The construction of the machine is not complex; the speed of transmission is considerably greater than has ever been previously attained by a facsimile telegraph; and the necessity of employing a chemically-treated paper is obviated. The transmitting and receiving machines nowise differ in construction; hence, one instrument can be used either for sending or for receiving a picture or a message.

The electrograph, as this new machine is called, is the invention of Herbert R. Palmer, M. E., Thomas Mills and Dr. William P. DunLany, and is made by the International Electrograph Company, of Cleveland, Ohio. The instrument consists of a substantial metal frame carrying a 110-volt, direct-current electric motor, the armature-shaft of which is connected by a reducing-gear with the shaft of a rotatable cylinder. The several gear wheels employed constitute a variable speed-gear, the elements of which are thrown into and out of mesh by means of a friction clutch in order to vary the speed of the cylinder's rotation. On its surface the cylinder carries either a transmitting or a receiving sheet (similar instruments being used at both the transmitting and receiving stations). In the machine illustrated the transmitting sheet is a zinc enlargement of a half-tone plate, the variations in the surface of the zinc sheet being considerably more pronounced than those of the smaller original, so that the transmission of the picture is facilitated. For newspaper work the enlarged picture received at the second station is to be reduced. Into the depressed portions of the zinc enlargement, corresponding with the etched portions of the original half-tone, an insulating material is filled. Thus treated, the zinc sheet presents a fairly smooth, partially metallic and partially insulated surface.

The filled zinc plate is curled around the cylinder of the transmitting machine; and upon the surface of the zinc plate glides a stylus which is caused to travel along the rotating cylinder by a carriage, very much as the reproducing stylus of a phonograph is caused to travel along a sound-record. Thus, the stylus comes into contact with every portion of the cylinder surface, describing a continuous spiral as the cylinder rotates and the carriage travels. Upon a piece of ordinary paper wrapped upon the cylinder of the receiving instrument, many hundred miles away, plays an inked pen which, like the transmitting stylus, is caused to travel along the paper of the rotating receiving-cylinder. Since the same instrument can be used whether for transmitting or receiving messages, the carriage is provided with both a stylus and a pen, so mounted that either can be thrown into or out of operative position. The stylus, as the cylinder rotates, glides over a surface partially metallic, partially insulated. When in contact with the metal, the circuit through the line and receiving instrument is completed, and a line or dot is traced by the pen of the reproducing instrument corresponding in length with that traced by the transmitting stylus. When the stylus is in contact with an insulated portion of the zinc sheet, the circuit is broken and the pen of the receiving instrument is withdrawn from the paper. The pen of the receiving machine is actuated by electro-magnetic coils, affected by the make and break of the circuit, reproducing the dots of the half-tone plates. These coils are operated up to a speed of 150 impulses per second without perceptible lag, and without a retracting spring. The pen is lifted from the paper with a speed equal to that of its closing impulse. In this way, high speeds with very weak currents can be attained. This is accomplished by opposing to the main operating coils a pair of smaller coils, shown in detail in Fig. 1. Both coils are electrically in series, and energized at the same instant. The armature, carrying a common steel pen, vibrates between these opposing coils. The main, or recording, coils are wound upon cores of soft Swedish iron, while the others have cores slightly harder, with a greater magnetic lag. The effect produced by the current energizing the coils at the same instant is to pull the armature toward the quicker, the recording pair, where it is firmly held, owing to its increased distance from the opposing pair. On breaking the current the recording coils, discharging first, weaken sufficiently to enable the magnetism still remaining in the opposing coils to withdraw the armature to its original position. Hence a retracting spring is not necessary, and the current, having no force to overcome while producing motion in the armature, can be very weak, and still make a perfectly black ink mark on the paper, an operation much appreciated by telegraph engineers.



Fig. 1.—THE CARRIAGE, SHOWING MAGNETIC COILS, STYLUS, AND PEN.

Fig. 2.—PORTRAIT OF PRESIDENT LOW, TRANSMITTED BY THE ELECTROGRAPH. (Reduced.)

Good results are secured with a current of 110 volts passed through 20,000 ohms of line resistance, which is equal to 4,000 miles of No. 10 copper circuit, earth return. The internal resistance of the machine is 250 ohms. Over an actual telegraphic line some 770 miles in length, extending from St. Louis to Cleveland, by way of Chicago, the machines operated faultlessly. When Western Union telegraphic repeaters are used the speed of transmission is reduced by two-thirds; but in ordinary transmission it is customary to cut out all repeaters.

It is clearly necessary to synchronize the two rotating cylinders so that the picture may be exactly reproduced. For this purpose resistance-coils are employed, which can be cut in and out of the field of the motor, together with a simple synchronizing device. The synchronizing is effected by an automatic three-way key, which cuts synchronizing coils into the circuit once during each rotation of the cylinder. The fast cylinder stops, and starts immediately upon closing the automatic key in the slow machine. The completion of the circuit which thereby results opens a lock on both machines, starting both cylinders at the same instant. All differences of speed are corrected at the end of each revolution. An accumulation of errors is, therefore, obviated.

A picture is sent at the rate of one inch per minute



Fig. 3.—FRONT VIEW OF ELECTROGRAPH.



Fig. 4.—REAR VIEW OF ELECTROGRAPH.

© 1901 SCIENTIFIC AMERICAN, INC.

of the cylinder length; that is, a picture or cut which occupies the whole length of the cylinder, 8 inches, will be transmitted in 8 minutes time. In the reproduction of a very fine-meshed picture, the stylus of the transmitting machine and the pen of the receiving machine will rule 80 lines per inch. Coarser pictures are transmitted at the rate of 40 lines per inch, or in 4 minutes. The space occupied by a cut in a newspaper could be filled by an equivalent number of words telegraphed by an ordinary operator at a speed of 25 or 30 words per minute. Hence, the time required in transmitting a picture by means of the electrograph is exactly the same as that consumed in telegraphing a verbal message. About 40 minutes are required to prepare the zinc plate for transmission and about 30 minutes to prepare the picture reproduced by the receiving machine for newspaper printing. On a 1,500-mile circuit 80 minutes suffice to prepare a zinc enlargement, transmit the picture, and reduce the picture reproduced for the press. Of this time not more than 10 minutes are consumed in transmission. Machines with cylinders thirty inches in length, having two carriages, are now in the course of construction and are to be used in duplex transmission, one picture being sent simultaneously each way over a single wire. A machine thus receives and sends a picture at the same instant. With two instruments at each end of the line, a quadruplex transmission is possible, four pictures being sent over the wire simultaneously. Thus the average time of transmitting a picture is reduced to two minutes' wire service. That these speeds can be practically attained has been proven time and time again by severe tests made over the Western Union, American Telephone and Telegraph Company, and the Associated Press wires.

FLOOR SYSTEM OF THE NEW EAST RIVER BRIDGE.

In comparing the greatest bridges of the world—and it seems as though we can only arrive at a correct idea of the proportions of one of these great structures by expressing it in terms of some other one—it is impossible to say of any particular bridge that it is, in the total, the greatest of its kind. One bridge may have the longest single span, and another the greatest number of extremely long spans; to another may belong the distinction of having the greatest carrying capacity, while a fourth may be distinguished by the magnitude of certain parts, such as the foundations, which are entirely hidden from view. In respect of the length of its main span, the present Brooklyn Suspension Bridge is practically the equal of the new East River Bridge, the new structure having a span of 1,600 feet between towers and the older bridge being five or six feet less. In over-all measurement, indeed, the Brooklyn Bridge greatly exceeds the new structure, the distance from anchorage to anchorage being 3,455 feet 6 inches, whereas the distance between anchorages of the East River Bridge is about 675 feet less than this. Although the total length of the steel structure of a bridge is what we might call the most spectacular feature of its measurement, the true test of the capacity of these modern, long-span bridges is the width of the floor system, or its capacity for traffic. Judged on this basis, the new East River Bridge is considerably the largest structure of its kind in the world.

With a view to giving the reader an adequate impression of the carrying power of the new bridge, our artist has prepared the cross-sectional view which is found on the front page of this issue. The section is supposed to be taken at a point about a third way across the main span, starting from the Brooklyn tower. As the parts of the bridge at the point of section are shown to exact scale, the drawing not merely affords an admirable perspective view of the finished structure, as it will appear to a passenger in crossing the bridge, but it shows with great detail the exact proportion of the various members, the method in which they are assembled, and the functions which they severally perform. For purposes of comparison it may be mentioned that the extreme breadth of the suspended structure of the Brooklyn Bridge is 85 feet; whereas the extreme width of the floor of the new East River Bridge will be 118 feet. The total width of the latter is about evenly divided into five separate roadways. Of these, the center roadway, which is devoted to the elevated cars, contains two tracks, one for east-bound and the other for west-bound traffic. On each side of the elevated tracks are two street-railway car tracks, while beyond these, on the extreme outside of the bridge, are two carriage roadways. Above the street railway tracks are two platforms, each divided at about its center by an iron railing. Of the four roadways thus formed those on the outside are devoted to bicycle traffic, while the inside roadways are given up to foot passengers.

The great load of the suspended roadway is carried by four steel wire cables, in each of which there are 10,397 wires, 0.165 inch in diameter. The wire has a breaking strength of 100 tons to the square inch. The floor system is suspended from these cables by steel wire ropes, 1¾ inches in diameter, which are carried up and over steel saddles clamped upon the main cables. Each suspending cable is continuous; that is to say, it is carried over the cable saddle and below a bottom suspension saddle, the two ends being coupled in a sleeve. Two heavy inverted steel U-bolts depend from each bottom suspension saddle and are bolted beneath the covering plate of the bottom cords of the trusses.

If the floor system of a suspension bridge were at all times equally loaded from end to end, there would be no danger of a deformation of the cables, and the floor would maintain a true surface. But since the traffic is liable to be concentrated or "bunched" at one or more positions on the bridge, it is necessary to stiffen the floor system to resist the vertical distortion which would otherwise result. This stiffening is afforded by two massive stiffening-trusses, each 40 feet in depth, which extend entirely across the bridge from anchorage to anchorage. These trusses are located immediately on the outside of the street railway tracks, and lie in a vertical plane between them and the carriageways. The bottom chord of the truss is of the same depth as the floor system into which it is built, and with which it is firmly incorporated. The floor proper of the bridge consists of a series of transverse plate-steel girders, 5 feet in depth, which extend entirely across the floor from side to side. These girders are placed 20 feet apart and the gaps between them are bridged longitudinally by lines of plate-steel stringers, of about half the depth of the floor beams. There are twenty of these lines of stringers counted across the width of the bridge, and they extend entirely throughout the structure from end to end. The load of the roadways is carried by the overhanging, cantilever-like, ends of the floor beams, and the middle portion of the floor beams between the stiffening trusses is supported at two intermediate points from a series of overhead trusses, which are built in between opposite panel-points of the top chords, at every 20 feet of the length of the bridge. The advantage of this method of construction is that it saves weight, and also enables the floor beams to be made many feet shallower than they would have to be were they not thus supported.

The stiffening trusses are constructed on the riveted system in preference to the eyebar system, which was at one time so greatly in vogue as to be considered the typical American construction. As a matter of fact, in the whole of this bridge, there is not, as far as we know, a single eyebar used, except at the anchorages, where eyebar chains extend through the masonry to take hold of the anchorage platforms. The web members of the stiffening trusses are arranged on the triple-intersection plan and they consist, as do also the members of the lateral system, of heavy angles placed back to back and latticed together. The bicycle and foot-passenger platforms are carried upon plate steel floor beams which are supported at their outer ends by the web members of the stiffening trusses and at their inner ends are riveted to the vertical ties connecting the overhead trusses with the floor beams.

In a suspended structure of this great span, presenting such a large total area to the pressure of the wind, it becomes necessary to make special provision to resist wind stresses. As far as the floor system is concerned, this provision consists of a heavy horizontal system of trussing between the top chords of the stiffening trusses, while in the plane of the floor of the bridge sufficient resistance to lateral distortion is afforded by the manner in which the longitudinal stringers are riveted intercostally between the floor-beams; the tensional stresses, due to a wind blowing transversely across the bridge being resisted in the leeward half of the floor by the stringers and the bottom chord of the stiffening truss, and the compressive stresses being similarly resisted by the stringers and bottom chord of the windward half of the floor system. The wind stresses are also resisted by the "cradling" or inclining together of the cables.

The upper view of the East River Bridge on our front page was taken from a position slightly to the rear and to the side of the Brooklyn anchorage. The cables, which are shown stretched in position, are those which have been strung for the purpose of carrying the temporary platform, from which the four main cables will be constructed. The latter will be assembled and the wrappings and clamps put on at an elevation slightly higher than that at which they will be finally suspended. When they are completed the temporary platform cables will be removed, and the main cables will be lowered to their permanent position. The next step will be to hang the suspending cables upon the main cable saddles, and then to the lower end of these will be gradually attached and built together the heavy framework of intersecting floorbeams and stringers. Upon the foundation thus prepared will be erected the great 40-foot stiffening trusses, with their intermediate trusses for carrying the railway tracks and the passenger platforms.

Engineering Notes.

A large seven-story building in Chicago has just been raised without cracking a pane of glass or marring a wall. The building was raised 21½ feet with the aid of a steel sub-structure and 1,500 jacks. The work was completed in twenty-one days.

Consul General Guenther, of Frankfort, reports that on the 20th of March official tests of so-called fireproof stairs for apartment houses were made at the yards of one of the fire-department stations in Frankfort, where intense fires had been started for the purpose. The stairs covered with plastering showed the longest resistance and could still be used after being subjected to the fire for twenty-five minutes. Of stairs coated with fireproof paints, no tangible results could be stated, as the stairs experimented with were of great variety as to material and strength; but they were still serviceable after five or ten minutes under fire. Of the wooden stairs without fireproof paints, those of oak withstood the fire the longest.

On March 1 a mail train, consisting of engine, mail car, baggage car, and sleeping car, was run over the Savannah, Florida & Western Railroad from Fleming, 24 miles south of Savannah, to Jacksonville, Fla., 149 miles, in 130 minutes, or at the rate of 68.8 miles an hour. This time includes one stop, and there were two other places where speed had to be slackened. It is stated, says The Railroad Gazette, that the time taken in covering five miles between the sixty-ninth and the seventy-fourth milestones was 2 minutes 30 seconds, a speed of 120 miles an hour. The engine was a ten-wheeler, burning bituminous coal. It weighs 65 tons, of which 48 tons is on the drivers. The cylinders are 19 inches by 28 inches, and the driving wheels are 73 inches in diameter. The boiler is the extended wagon-top type, with 300 flues 2 inches diameter and 14 feet long.

An expedition of a private character dispatched from Norway last summer to Spitzbergen to exploit the coalfields there, has returned to Throndhjem with good results. In Advent Bay large coalfields were discovered and seized, and some 500 hectoliters brought home as a sample. The coals, which are said to resemble anthracite, are reported by experts to be of good quality. A company is in course of formation in Throndhjem in order to work these coalfields. In addition, a cargo of coals has been brought from the well-known deposit at Cape Boheman, and they have been tried on the state railways and otherwise. The drawback to these coals is, however, that they leave a very large quantity of porous slag in the furnaces, and are quite unsuitable for locomotives. The slag, or deposit, of scoria would also prevent the use of the coals for domestic and factory purposes.

A machine for extinguishing fires in ships' holds recently introduced into Great Britain depends for its action on the generation of sulphurous acid gas, which is forced into the chamber in which the conflagration has occurred, and which, by replacing the air, so vitiates the atmosphere that combustion cannot continue. The machine consists of a generating chamber, into which air is forced by a fan, and in which a store of sulphur is placed. This can be simply ignited by throwing upon it a piece of burning waste. The gas thus generated is forced into the chamber, and after a while extinguishes the flames. Attached to the apparatus is also a condenser, by means of which, the fire once extinguished, the gas is passed through and through the chamber as it cools, until the materials which have been burning are reduced to such a temperature that they do not burst into flame when the air is at length introduced. This is brought about by a gradual process.

A series of interesting experiments on the explosive effects of the modern infantry bullet have been carried out in Germany by C. Cranz and K. R. Koch, says Nature, London. They used a new Mauser rifle of 6 millimeter (½ inch) bore, having a muzzle velocity 100 meters (328 feet) greater than model 88. To imitate the effect upon large bloodvessels, while at the same time obtaining simple physical conditions, the experimenters constructed short, hollow tin cylinders filled with water, and closed at one end with a sheet of rubber and at the other with a sheet of parchment paper. Electrodes were mounted before or behind the cylinders, or inside them, and the discharge spark produced by the bullet was utilized to obtain a photograph of its silhouette at various points of its path. Among the important facts thus elicited it appears that the body struck is not displaced by the entry of the bullet. On leaving the body, the bullet carries away with it a small part of the hind surface, having a small round perforation through which the bullet passed. The explosion does not take place until the bullet has left the body. After discussing the evaporation, hydraulic pressure, rotation, and sound-wave theories of the explosion, and discarding them all, the authors conclude that the apparent explosion is due to the transfer of kinetic energy to the portions hit at later stages, which are thus torn away from those first encountered.

© 1901 SCIENTIFIC AMERICAN, INC.

Correspondence.

Sun Motors for India.

To the Editor of the SCIENTIFIC AMERICAN:

In one of the recent issues of your paper which has come to hand is found the article, with illustrations, on solar motors. This has proved of great interest to me, as the thought has suggested itself time and again in this severe famine, "Why cannot some means be employed for the utilization of the fierce heat of the sun for the purpose of pumping water?" This article goes to show that the day is not far distant when a great deal of heat will be derived from the sun.

I shall watch with keen interest the development of the solar motors and do what I can to let it be known here that the Americans are successfully creating power from the sun's rays.

Undoubtedly these motors will command world-wide attention, as there are vast tracts of territory where the cloud percentage is very small and where, could power but be obtained, "the desert would bloom as the rose." In this portion of India the season in which water is most sorely needed, especially after the failure of the rains, is called "sun time." The percentage of sunshine is very high.

A few figures from some experiments I have made with respect to the power of the sun may be of interest to those who are constructing the "motors." From these it would appear that the heating power of the motors would be increased should the "magic circle," or possibly the entire middle portion of the motor be incased with glass.

The following are the figures recorded on three separate days, with an ordinary thermometer, in the sun at midday, and the temperature in a cardboard box covered with glass. Had a tin box been used a still greater difference would have been recorded:

	In Sun.	In Glass-Covered Box.	
April 17, 1901	126°	157°	= + 31
April 19, 1901	130°	157°	= + 27
April 22, 1901	127°	159°	= + 32

From these it will be seen that the temperature in the box was from 27° to 32° higher than in the open air. Should the temperature in the "magic circle" be raised from 27° to 32° by simply incasing the same in glass, undoubtedly better results would be obtained.

REV. WALTER T. SCUDDER.

Vellare, India, Madras Pres., May 1, 1901.

Meteor Seen in Daylight.

A remarkable phenomenon, that of a meteor seen in daylight, was observed in different localities in the northwest of Germany on the 16th of December last. According to the indications furnished by Das Wetter, the meteor was observed about 4.40 P. M., near 45° above the horizon, in the direction south-southeast. It appeared under the form of a large mass of a brilliant and rather violet hue; it moved in an arc which was somewhat inflected toward the horizon, in the direction southwest. The meteor disappeared at or near the horizon, according to the different reports. The light was quite intense, as may be remarked from the fact that even in daylight the phenomenon was mistaken for that of lightning. The observers agree in attributing to the meteor an elongated and pointed form, but this may have resulted from an optical illusion due to the movement. The meteor in its passage through the atmosphere left behind it a great quantity of smoke or vapor, which was visible in the form of clouds extending nearly five minutes of arc in length behind it. These clouds, which were visible in spite of the rays of the sun, which had not set, followed the path of the meteor at first, but then moved toward the east in the direction of the wind, and gradually settled down, this no doubt being due to the weight of the particles composing them.

A Derailment That Damaged a Pond.

A curious case was brought before the Supreme Court of Pennsylvania recently, says The Railway Gazette. Plaintiffs owned an ice pond and brought an action for $7,500 damage to 15,000 tons of ice, due to 6,000 gallons of oil from an oil tank car which had been derailed. The derailment, according to the evidence, was not due to any fault on the part of the defendant. The oil ran through a break in the tank at the rate of two gallons a minute, and flowed into plaintiff's pond. The defendant used every effort to pump the oil from the car into another car without success, and at the end of eleven hours from the time of the accident, the defendant, finding that nothing could be done to save the oil, opened the valve at the bottom of the tank and let it all run out. The court said, in refusing to permit a recovery by the plaintiff, that as the quantity of oil which had already flowed into the stream was sufficient to render the ice made from its waters useless, letting out the remaining oil is an insignificant fact, and cannot be said to be sufficient to place the responsibility on the defendant. (Commercial Ice Co. vs. Reading.)

Electrical Notes.

Germany and Holland are planning to lay a new cable to connect with the Dutch East Indies.

There are now in Italy 3,179 kilometers of street tramways worked by mechanical power, 263 kilometers of these by electricity, and the remainder by steam power. They are owned by 64 companies and private concerns. The town of Milan owns only 5½ kilometers, while the two largest companies control 261 and 205 kilometers respectively.

A committee of experts appointed by Postmaster-General Smith, which investigated the workings of the pneumatic tube systems of carrying mails in cities, has reported its conclusions that on the present basis of cost the system is too expensive. They say, however, that a system to be operated by electricity is in process of development and bids fair to be successful. It essentially consists of a miniature third-rail trolley road operated in a tube.

A large electric plant is being erected at Bibi-Eybat, near Baku, which is intended to supply power and light for the whole district where boring operations are carried on. There are four dynamos of 500 kilowatts and 2,000 volts each. All the necessary work, including boring, will be done with electric motors, and these are of a particular construction. Great care is taken to exclude the highly inflammable gas, rising from the borings, from the motors and other parts likely to cause an explosion.

At a meeting of the German Auer Company, held some time back, it was announced that Dr. Auer had succeeded in making an electric lamp with a filament of osmium, says The Trade Journals Review. It was further stated that laboratory experiments showed this lamp to take but 1.5 watts per candle power, and that the average life would be not less than 700 hours. The lamp works best, it is said, with a small electromotive force, 25 to 50 volts at most. This, while an inconvenience in most cases, has advantages when the lighting current is supplied by batteries, since fewer cells are needed.

A light electric railway for passengers and goods traffic in Russian Poland, connecting the towns of Lodz, Zgierz, and Pabianice, is now open. Its length is about 21 kilometers, and the electric plant has been built in Russia. The line is owned by a company consisting of Polish manufacturers and merchants, and has cost about £80,000. The building of this railway has been granted by the Russian government on the conditions that after twenty-eight years the whole line and plant is to be handed over to the government without any compensation, and that after twenty years it has the option of purchase. Furthermore, the company has agreed to pay a certain portion of the profits to the government. This line is interesting, as it is the first electric railway established in Russia.

Several French syndicates have planned the development of the water power of the Rhone, and extensive plants are to be erected within the next three years between Pyrimont and the Swiss frontier. The first of these projects is that of Malpertuis, 2½ miles below Bellegarde, where the river falls thirty to thirty-five feet, with perpendicular banks only 160 feet apart. By building a tunnel one-half mile long, a total fall of fifty-one to fifty-five feet can be secured, equivalent to 25,000 horse power, at low water. Near Bellegarde another tunnel would secure a fall of eighty to eighty-five feet, developing 30,000 horse power. And about eight miles from the Swiss frontier is a narrow gorge only 80 feet wide, and a dam built here would give a fall of sixty-five feet, or 30,000 horse power, at low water.

It has been noticed in certain parts of America and in India, that during thunderstorms incandescent lamps that are alight suddenly brighten up very considerably, in some cases sufficiently to break the filament; and in some cases the brightening is followed by the lamp's giving an inferior light to that which it gave previously to the storm. It has been suggested that this phenomenon is due to a similar action to that which takes place in the coherer, which is used in the high-tension form of wireless telegraphy, viz., a closing up of the molecules, and a corresponding decrease of the electrical resistance of the filament, this having been observed in coherers, when thunderstorms have passed over the places where they were fixed. It appears more likely, however, that it is due to pressures induced by the passage of charged clouds over the lines connected to the lamps, the increased brightening taking place when the induced pressures were in accord with the service pressures.

Robinson Crusoe's Gun.

A Philadelphia firm of auctioneers recently offered at one of their sales Robinson Crusoe's musket. It was a fine old flintlock. It was in the possession of a grandniece of Alexander Selkirk, and its pedigree is much more unclouded than is usually the case with objects of this kind.

Automobile News.

The progress of the automobile industry in France will be seen from the following table, which gives the figures for imports and exports of automobiles, cycles, as well as private carriages, for the years 1898, 1899 and 1900:

IMPORTATION.	1898.	1899.	1900.
Automobiles	$79,010	$94,530	$101,800
Cycles and motocycles	1,785,060	1,588,810	1,107,360
Carriages	172,870	159,960	122,400
EXPORTATION.			
Automobiles	$349,870	$851,860	$1,882,000
Cycles and motocycles	2,132,800	2,030,710	1,583,800
Carriages	431,460	854,800	610,720

It will be seen from the table that the figures for the imports and exports of last year have diminished for cycles and motocycles, as well as for carriages. The figures for automobiles, while increasing somewhat in importation, have more than doubled in exportation. It is estimated that more than 3,000 workmen, at a mean of $1.60 per day, have been occupied during the whole of last year upon foreign orders alone. It will thus be seen that the automobile industry is in a flourishing condition.

The Paris-Berlin and Paris-Bordeaux are the two next important races; the latter includes the Gordon Bennett Cup, which will be run on the same day. The Paris-Berlin has been organized by the Automobile Clubs of France and Germany, in connection with the Belgian Club and the Union of German Automobile Clubs. The distance will be covered in three stages. 1. 27th of June, Paris-Aix-la-Chapelle, starting at 3:30 A. M. 2. Aix-la-Chapelle-Hanover, the following day; start at 5 A. M. 3. Hanover-Berlin, the 29th, starting at 5 A. M. After the machines arrive at Berlin they will be taken to a large building which has been prepared, and will form part of an automobile show to be held on the 30th of June and the following day. The race is international, and includes the usual four classes of moto-cycles, voiturettes, light and regular machines; the last two classes carry at least two persons, representing 154 pounds each. Engagements may be made up to the 25th of June ($10 to $60, according to class), but this is doubled after the 27th of May. A considerable number of entries have been made up to the 12th of May, including Charron, Levegh, De Knyff, Heath, Count de Chasseloup-Laubat, Girardot, Count Zborowsky, etc., with petroleum machines; Jenatzy, with an electric racer; Serpollet (steam system), and others.

The Automobile Club of Great Britain has organized a competitive test of automobiles for the 13th of April, which takes the place of the first test of alcohol motors, this having been postponed to a later date. In the present tests the speed of the machines is not taken into account, but only their general performance. The meeting of the participants takes place at the Sheen House Club, and the start is at 2:30 P. M. The route includes a part of Richmond Park to Robin Hood Gate, Kingston, Esher, Cobham, Weybridge Road and return by Hersham, High Road, Roehampton Lane and Richmond Road, arriving at the starting point after having covered exactly 30 miles. The event is terminated by a dinner given at the Sheen House Club, in which the organizers and competitors are united. As regards the three-monthly tour for the Hundred Miles Record, organized by the Automobile Club for the 2d of April, this event could not be carried out with great success owing to the bad weather, and out of 12 engagements only 2 were present at the start, these being a machine of the Gladiator (French) type, new model, with a 6 horse power water cooled Aster motor, and an English machine, a 6 horse power dog-cart of the Marshall type. The weather was not favorable for the test, as a violent wind which blew during the day made the trip difficult. This was over the Kensington route, *via* Uxbridge, Beaconsfield, High Wycombe, and return. Both machines, however, made a good performance; the official record has not yet been made public. It is to be expected that the next contest, which takes place on the 2d of July, will be more successful.

A New Ruling on Patent Rights.

A ruling of Judge Kohlsatt in the United States Circuit Court is most important, as it makes valueless a patented device which has been used solely in a business not recognized by law. The plaintiff lost his case "in view of the lack of legal utility of the patented device." The case in point was a patented bogus coin detecter used in slot machines operated for gambling purposes. The decision by Judge Kohlsatt deprives the owner of the patent of standing in a court of equity to sue any man for alleged infringement on the device. The judge held that the patent in this case was not useful to the world in general and that the patent rights therefore could not be protected.

It is estimated that the cost of restoring the papal palace at Avignon, France, would be about $1,400,000.

© 1901 SCIENTIFIC AMERICAN, INC.

A CHINESE TELEPHONE SYSTEM.

What is said to be the only Chinese telephone system in the world is in operation in the city of San Francisco. There are altogether about 18,000 Chinese citizens, of whom 1,500 are merchants. Of this number 270 are subscribers to the telephone.

These Chinese merchants were prompt to understand the saving of time and great convenience in the use of the instrument. Though looked upon, for a time, with some superstitious dread, familiarity has accustomed the people to its use and it has now become an indispensable concomitant of the regular office equipment. The central office heretofore has been too small to allow any increase of the subscribers, but the company has recently acquired a property and is fitting it up so as to accommodate any number. It is expected that with greater facilities twice as many instruments as are now in use will be installed.

The system in Chinatown is entirely independent and is for the Chinese only. To communicate with outside subscribers a separate charge is made. A white merchant using the Chinatown system must also pay extra. The Chinese subscribers can and do use the long distance wires upon payment of the customary charges.

Altogether there are seven Chinamen employed in the office, a chief operator and three assistants, besides three messenger boys who are on duty day and night, the office being never closed. In respect to facility the Chinese telephone operators are quite equal to the whites.

It is said that the voice of the Chinaman is superior to all others in the distinctness with which it can be transmitted by wires. In calling subscribers the operator, instead of using numbers to designate each one, as customary among the whites, is compelled to call the names of the individual or firm that is wanted, a feat of memory of which only a Chinese operator is capable; and not only, it is said, is he equal to this, but also carries in his mind the probable haunt of the man required should he be unable to ring him up at his regular place of business.

The operators of the Chinatown system are in no relation to the metropolitan office. They are hired and paid by the Chinaman who controls it. The main company install the instruments and keep the wires in repair, allowing their Chinese agent a certain amount for each subscriber, the agent collecting the bills and securing new subscribers.

The San Francisco experiment has proved a successful one financially and is extremely popular among a people even as loath to accept new ideas as Chinamen are; and it is believed that one result of the local experiment will be the early introduction of the telephone throughout the whole Chinese Empire as soon as conditions of peace are assured.



A CHINESE TELEPHONE CENTRAL OFFICE IN SAN FRANCISCO.

THE NEW EDISON STORAGE BATTERY.

Probably no invention of recent years is of such vast electrical importance as the new accumulator which Thomas A. Edison has added to our store of electrical devices. Electricians were most agreeably astonished when Dr. A. Kennelly confirmed the rumors which had been rife many months, and gave the first full, clear description of the battery in a paper read before the American Institute of Electrical Engineers. The paper was published in last week's SUPPLEMENT and editorially discussed in these columns, so that our readers are now more or less familiar with the cell. Through the courtesy of Mr. Edison we were enabled to examine the battery, to prepare the drawings which accompany the present article, and to give some additional information which may prove of interest.

For the new cell an absence of deterioration is claimed which has never been characteristic of the most approved lead batteries. Its storage capacity per unit of mass is said to be unusually large. The time required for charging and discharging is exceedingly short. To these merits must be added cheapness in manufacture and durability. The negative pole or positive element and the positive pole or negative element are both similar in construction and respectively composed of iron and superoxide of nickel. When placed in their containing-cell the plates are separated by sheets of gutta percha. The electrolyte of this nickel-iron battery is a solution of potassium hydroxide. Each plate consists of a sheet of steel, 0.024 inch in thickness, perforated so as to form a grid with rectangular holes. In each opening of the grid a pocket or shallow box containing the active material is placed. In order to enable the electrolyte to reach the active material the boxes or pockets are perforated with many holes so as to form a kind of screen, which although it conceals the active material, permits the free entrance of the electrolyte.

The boxes or pockets consist of perforated crucible steel cut from a long strip 0.003 inch thick. To fit these boxes the active material is hydraulically compressed in the form of briquettes.

The positive briquettes are composed of a finely-divided compound of iron and a nearly equal volume of thin flakes of graphite. The negative briquettes are composed of a finely-divided compound of nickel and an equal quantity of fine flakes of graphite. In both plates the graphite does not enter into any of the chemical actions, but merely assists the conductivity of the briquettes. The iron and nickel compounds used are obtained by special chemical processes.

Each briquette when placed in its box is covered by a lid fitted over the box or pocket, so that the briquette is closely enveloped on all sides. Thus prepared, the boxes are placed in the openings or holes of their respective grids; and the assembled plates are thereupon subjected to a hydraulic pressure of some 100 tons in order to close the boxes and to force their metal sides over the adjacent sides of the recesses of the steel grid. A single, solid steel plate is thus produced. Both grids and boxes are nickel-plated in order to secure a good electrical connection between them. At any point the maximum grid thickness, after hydraulic pressure has been applied, is 0.024 inch, the pocket thickness being 0.1 inch. The cell in which the assembled plates are contained is composed of sheet steel containing the potash solution.

The charging current deoxidizes the iron compound to spongy metallic iron and conveys oxygen through the electrolyte to the nickel compound, forming a hyperoxide of nickel. In discharging, the current passes from the positive pole and through the external circuit to the negative pole and its attached iron or positive plate, and then through the solution to the superoxide plate, causing the oxygen to move back against the current and partially to reduce the nickel to superoxide, and to oxidize the spongy iron.

Since the potash solution theoretically serves as a conveyor for the oxygen, the amount of solution required is merely that which is sufficient to wet the negative material. The plates are hence packed as closely together as possible, because there will be less resistance and less weight.

The initial voltage of the discharge is 1.5 volts; the mean voltage of full discharge is approximately 1.1 volts. The storage capacity of the cell per unit of total mass is 14 watts per pound or 30.85 watt hours per kilo. The mean normal discharge of the power-weight per unit mass of total cell is 4 watts per pound, or 8.82 watts per kilo, corresponding with a normal discharge period of 3½ hours. At a high rate, however, a cell can be discharged in about one hour. Charging and discharging rates are the same. Overcharging or discharging affects only the electrical efficiency. No active material is ejected from the briquettes even under deliberate overcharging and discharging. Whatever gas is produced appears externally.

Changes of temperature seem to have no effect upon the cell. The electrolyte does not corrode any of the parts. The electromotive force being below that necessary to decompose water, no local action apparently occurs. Mr. Edison claims that a charged or discharged negative nickel plate can be removed from the working cell and dried in the air for a week, apparently without injury, and that when restored its charge seems practically undiminished. On the other hand, the positive iron plate if subjected to similar treatment soon loses its charge by the oxidation of the spongy iron, with a liberation of heat and an appreciable rise in temperature. When replaced, however, in the cell, the storage capacity of the plate is unaffected on recharge. According to Dr. Kennelly, Mr. Edison hopes to manufacture the new cell at a cost which will not exceed that of the lead battery.



THE EDISON STORAGE BATTERY—SHOWING ALSO GRID, POCKET FOR ACTIVE MATERIAL, AND PORTIONS OF GUTTA PERCHA PARTITION.

Zeper calls attention (Klin. Monats. für Augenheilk.) to the irritation of the conjunctiva, often amounting to conjunctivitis, and to the severe itching of the hands and face, which attack the workmen employed on the large bulb farms in separating dried hyacinth bulbs in August and September. The author attributes this to the presence of an acarus which he considers may work its way under the skin, but he also mentions the fact that masses of brittle crystals are found on the bulbs, the cells of which are well known to contain many raphides, and it is possible that those entering the skin may give rise to the irritation described.—Bost. Med. and Surg. Journ.

Freight can be carried on trolley cars within the city limits of Detroit.

© 1901 SCIENTIFIC AMERICAN, INC.

THE NEW FLOATING DRYDOCK FOR THE UNITED STATES NAVY.

There is nearing completion at the establishment of the Maryland Steel Company, at Sparrow's Point, Md., a steel floating drydock which is intended to be located upon completion, at the United States Naval Reservation at Algiers, La., opposite New Orleans. Its length is 525 feet over blocks; it has an entrance of 100 feet in the clear between walls, and will have a maximum lifting power of 18,000 tons. It will be attached to two steel columns on shore by two steel lattice booms, articulated in all directions. The dock will, therefore, be free to rise and fall with the river, which is subject to frequent severe freshets, and sometimes rises to 20 feet above Gulf level. This connection will, at the same time, allow the dock to be swung inshore out of the worst of the current, which occasionally attains a speed as high as six miles an hour.

The general plans of the dock were made by Clark & Standfield, of London, England, who were the designers of many similar docks, the principal of which was the one constructed for the Spanish government, built by Swan & Hunter, of Wallsend-on-Tyne, England, and towed to Havana, Cuba. Another large dock of the kind is a commercial dock, which was also built in England, and was towed to Stettin, Germany. Several modifications and improvements were added to the first plans submitted, to meet the requirements of the Bureau of Yards and Docks, the details of these improvements being worked out by the engineering department of the Maryland Steel Company. Among other changes the structural strength throughout the



END VIEW OF THE ALGIERS FLOATING DRYDOCK, WITH A 15,000-TON BATTLESHIP SHOWN IN OUTLINE.

pontoons was increased, giving the dock a maximum capacity of 18,000 tons when the deck or floor is awash, or of 15,000 tons with a freeboard of about 2 feet.

The specifications with these changes included call for a transverse strength sufficient for docking a battleship of 15,000 tons with the entire weight carried on the keel blocks. The specifications require that the time required for lifting a vessel shall be 3½ hours from the time the keel is centered on the blocks.

The mention of the question of the lifting power forms an opportune occasion for pointing out how comparatively little power is expended by a floating dock in lifting a vessel in a given time. When docking a vessel in a graving dock the whole of the contents less the volume of the ship has to be removed by pumping; therefore the smaller the ship in dock the greater the amount of water to be removed; moreover, when it has to be emptied, merely to prepare a berth for a ship, the whole amount has to be extracted. In a floating dock, on the contrary, the ship being supported by the buoyancy of the dock, the weight of water to be removed is only proportional to the weight of the ship, plus an amount representing the dock itself, while when the dock is lifted light, to prepare the berth, only its own weight has to be dealt with. The saving thus effected is therefore very great and is not only apparent in the reduced first cost of the pumping plant, but remains constant throughout the dock's career, in the form of a reduced coal bill.

The following are the general dimensions of the dock:

Length over all	525 feet.
Breadth over all	126 feet 2 7-16 inches.
Breadth between walls	100 feet.
Depth over sills	18 feet.
Depth of pontoons	17 feet 6 inches.
Maximum draft	49 feet 6 inches.
Number of pontoons	3
Length of middle pontoons	242 feet.
Length of end pontoon	141 feet 3-8 inches.
Length of walls	395 feet 5-8 inches.
Total weight of dock	6,865 tons.

The dock consists of five portions, and comprises three pontoons as the lifting portion of the dock, and two side walls, which latter, while affording a certain amount of lifting power, primarily serve to give the dock stability and to regulate its descent when the pontoons are submerged. The pontoons themselves are of different sizes and form. The center one is 242 feet long and rectangular in shape, but the rectangular length of two terminal pontoons is only about 80 feet, the remainder being finished off in the form of a blunt nose-point or bow. For a length of 55 feet these end pontoons are buoyant, and the remaining length forming the point proper is formed by a series of plate and lattice girders of strong construction. Each pontoon has three longitudinal bulkheads, the two outer ones being watertight while the middle one is designedly left with small openings.

This central longitudinal bulkhead is intercostal between the transverse bulkheads, and has two vertical plates, connecting to the first and second intermediate frames by angles. These longitudinal frames are placed 2 feet 6 inches apart and are of a girder design, each frame calculated to withstand a strain of from 40 to 65 tons load per foot. This construction is carried throughout the entire central portion of all the pontoons, and covers the area required for affording the necessary stability for carrying the heaviest battleships now built. Thwartship bulkheads are introduced every 10 feet, every fifth and sixth being watertight. The side walls are similarly constructed with five transverse bulkheads, and are provided with two gangway openings on each side. These walls are connected to the pontoons by steel castings and fish plates, and secured together by taper pins and bolts.

The operating plant consists of engines, boilers, and pumps, which are installed in the two walls, each being a separate and complete plant within itself. The main pumps are placed in the bottom of the walls, and are connected by vertical shafting and gearing to engines which are of the compound type. They are furnished with automatic flywheel governors. A notable feature in the governing device of these engines is that the speeds of the pumps can be regulated with a variation of from 310 to 410 while the engine is in motion. The two side walls are also provided with flying gangways, which are placed at the bow end of the dock, and are hinged so as to swing together. They are provided with a platform and hand railing, which provides a means of passing from one side wall to the other. There are also on the inside of the side walls convenient ladders and stairways to reach the upper and intermediate deck from the deck of the pontoons. Each gangway deck and opening is provided with light swinging hand cranes for handling material from offshore connections or from lighters.

The actual mooring of the dock will be by four chair



THE NEW ALGIERS FLOATING DRYDOCK AS IT WOULD APPEAR WITH THE BATTLESHIP "MAINE" ON THE BLOCKS.

© 1901 SCIENTIFIC AMERICAN, INC.

cables of the stud-link pattern, to which will be attached mushroom anchors, the handling of which is done by heavy capstans connected to powerful winches; the cables are provided with coil-spring buffers where they make fast to the dock. There are also provided auxiliary winches, fairleads and all the necessary appliances for handling the lines for docking a vessel. The operating valve houses are located on the top deck of each side wall, from which position the entire manipulation in docking a vessel is conducted. Four mechanical side shores, two in each wall, are also operated from these top decks, so that a vessel can be easily and directly centered over the keel blocks.

An important feature of the dock is that any portion of it can be made accessible for repairs or inspection. To reach the bottom of one of the walls, say the port one, it is only necessary to heel the dock to starboard.

In the case of the pontoons, the middle one is made large enough to raise those at the ends out of water. Suppose it is desired to get at the bottom of the middle pontoon: the dock is allowed to float light; men then knock on the tapered pins of the two rows of fishplates which secure this pontoon to the side walls; then the dock is allowed to sink, the middle pontoon floating free, until the lower row of fishplates on the pontoons is level with the upper row on the walls; the pins are then driven in, the dock pumped out and the middle pontoon is lifted clear of the water. To unlock, the reverse course is followed. The end pontoons are similarly treated. The interior of the walls and pontoons is easily accessible through numerous manholes.

Should a disabled ship draw one or two more feet than the capacity of the dock permits, the dock master would not hesitate to sink the dock the extra depth, as the walls have a minimum freeboard of 4 feet 9 inches. Also, should a ship, from any cause, have a list, the dock could be given the same list within limits, the ship taken in, and the two then brought to an even keel.

It is a curious coincidence that the launch of two identical warships built for the United States navy should be taking place within a few weeks' interval at two establishments so widely separated as that of the Union Iron Works, San Francisco, and that of William Cramp & Sons, at Philadelphia. The "Ohio," recently launched in San Francisco by the President of the United States, is a sister ship to the "Maine," whose launch is scheduled to take place about the time that this issue will be in the hands of our readers. Another vessel which is being built from the same plans, and will be named "Missouri," will shortly be launched at Newport News, Va. As the "Maine" and her sisters are the largest vessels in the United States Navy, our artist has shown her docked in the new Algiers drydock; and it will be noticed that, large as this vessel is, she does not by any means exhaust the capacity of the dock. The principal dimensions of the "Maine" are, total length 388 feet, beam 72 feet 2½ inches, mean draft 23 feet 6 inches, displacement at mean draft 12,300 tons, full load displacement being 13,500 tons, or 4,500 tons less than the maximum lifting capacity of the dock. The contract speed is 18 knots. The "Maine" is surrounded at the waterline by a coffer dam filled with water-excluding material in the shape of a preparation of cellulose. The belt of side armor extends from 3 feet 6 inches above to 4 feet below the waterline. Amidships it is 11 inches in thickness at its upper edge and 7½ inches at its lower edge. A complete casemate armor belt, 6 inches in thickness, extends from the upper edge of the side belt to the upper deck. The vessel is armed with four 12-inch, 40-caliber guns, sixteen 6-inch, 50-caliber, rapid-fire guns, and six 3-inch 50-caliber rapid-fire guns; besides eight 6-pounders, six 1-pounders, two 2-inch field guns and two Colts. The 12-inch guns are carried in pairs in turrets protected with 11 to 12 inches of Krupp armor. The armored deck varies in thickness from 2¾ inches on the flat to 3 and 4 inches on the slopes. The supply of ammunition is plentiful—a most important feature in ships armored so largely with rapid-fire guns. The "Maine" carries 240 rounds for the 12-inch gun, over 3,000 for the 5-inch, 9,000 rounds for the 6-pounders and 4,000 rounds for the 1-pounders. The motive power is of the very latest type, steam being supplied by twenty-four Niclausse boilers with a total heating surface of 58,104 square feet. When the battleship is in commission, she will carry thirty-five officers and 511 men.

It is a fact not generally known that nearly all of the common lizards change color like the chameleon, but the change is less rapid. The ordinary fence lizard will be black after remaining upon black soil for about half a minute, but upon an old-fashioned rail fence the animal soon assumes the motley gray hue of a weather-worn rail. Upon a green leaf the same lizard will take on a decidedly greenish tint. The change of color, both in the chameleon and the common lizards, appears to be nature's subterfuge for the protection of the animal.

A SIMPLE BRICK-CARRYING DEVICE.

Our illustration pictures a clamp for carrying brick, which comprises essentially a turnbuckle engaged by oppositely-threaded shafts. Of these shafts one terminates in a grip and the other in a clevis. A bar is pivoted in the clevis and is provided at one end with a grip and at the other end with a handle and a loop.

The bricks are arranged side by side. By means of the oppositely-threaded shafts, the device is adjusted to pick up a certain number of bricks. The handle-bar is lowered, and the grips are slipped over the sides of the two end bricks. When the device



A NEW BRICK-CARRIER.

is lifted by the handle the grips firmly clutch the end bricks. The inventor of this brick-carrying implement is Frank E. Sproat, of Allegheny, Pa.

A SELF-MEASURING PUMP FOR LIQUIDS.

A pump which automatically measures the amount of liquid which it raises from a vessel is a novelty recently patented by Marshall Comincavish, a resident of the town of Fort Wayne, Ind.

Integral with the handle of the pump is a segment composed of two parallel parts straddling the piston-rod. The segment parts are provided with registering openings through which a pin may be passed, designed to come into contact with the piston-rod when the handle is raised and then limit the stroke of the piston. The bottom of the cylinder is perforated to receive a suction-pipe leading to the vessel containing the liquid. A valve in the suction-pipe is opened on the up stroke of the piston and closed on the down stroke. The liquid pumped in the cylinder is forced up into a goose-neck pipe connected with the cylinder and provided with a valve opened on the down stroke of the pump.



A SELF-MEASURING PUMP FOR LIQUIDS.

The short leg of the goose-neck pipe is composed in part of a glass-section to which a rubber tube is attached.

In operation the handle is raised until the pin strikes the piston-rod, thus limiting the stroke. On the upward movement of the piston liquid is drawn up into the cylinder. On the downward movement of the piston the liquid is forced up into and out of the goose-neck pipe, the valve in the suction-pipe being closed and that in the goose-neck opened.

The glass is used for sampling the liquid. This may be easily done by running a small quantity of the liquid into the rubber tube and squeezing the ends to retain the liquid. By detaching the tube the liquid may be tasted.

Electrolytic Apparatus for Hypochlorites.

In a recent article upon the electrolytic preparation of chlorates and hypochlorites on an industrial scale, M. Brochet describes several of the most recent forms of apparatus for the production of hypochlorites, these having a special value in the industries as being used to replace chlorine and chloride of lime for bleaching purposes. In the Hermite system, the electrolytic apparatus has anodes formed of platinum gauze held in ebonite frames. Between the anodes are placed the cathodes formed of zinc disks mounted on a shaft by which they are given a rotary movement; there are two such revolving cathodes for each pair of anodes. The shafts are mounted upon the top of the electrolytic tank, which serves equally as cathode. The solution used contains 50 parts of common salt and 5 parts of chloride of magnesium for 1,000 parts water. The apparatus forms mainly hypochlorous acid and magnesia, the latter being deposited upon the cathodes, from which it is removed by scrapers. The industrial apparatus of this type takes about 1,000 amperes at 5 to 6 volts, representing 8 or 9 horse power. It produces in 24 hours a solution which has a bleaching power equal to 275 pounds of chloride of lime, or 88 pounds of active chlorine. An apparatus of the Corbin type is used in a large paper works at Lancey (France). The electrodes are formed of platinum plates fixed in ebonite frames; these frames fit into the tank and divide it into compartments. The apparatus contains thirteen such plates and absorbs 120 volts and 150 amperes, or about 25 horse power. A dilute solution of salt, 2½ per cent, is used. The liquid circulates continuously; it comes out of a reservoir, passes into the electrolyzer, then into the bleaching vat, where it comes in contact with the wood-paste, which has been already partially bleached by the Mitscherlich process with bisulphite of lime. The vats measure 6 by 15 feet and 3 feet high; they contain 1,700 pounds of paste, which is made to circulate continuously by an agitator. The liquid is caused to circulate by means of a drum which takes it from the vat in a constant manner and sends it into a double-bottomed tank, from which it is raised to the first reservoir by a centrifugal pump. When the paste has remained long enough in contact, it is sent into the double-bottomed tank where it is drained. As it takes about 20 parts by weight of chloride of lime to bleach 100 parts of wood-paste, it results that each apparatus bleaching in 24 hours 1,700 pounds of paste, produces the equivalent of 330 pounds of chloride of lime, or 110 pounds of chlorine. The Kellner apparatus, constructed by Siemens & Halske, is used to a considerable extent in Germany. It consists essentially of an earthenware tank carrying on opposite sides a series of grooves in which slide a series of perforated glass plates, thus dividing the tank into twenty compartments of one-inch width. These glass plates serve as supports for the electrodes, which are formed of platinum gauze fixed on each side of the glass plate, and united by wires passing through the holes. The electrolyte is a solution of salt of 10 per cent strength; it enters at the bottom of the tank and comes out by overflow holes placed betwen the plates. The speed of circulation is regulated so that the liquid coming from the tank contains 0.05 per cent of chlorine; it then descends to a lower chamber containing a spiral of hardened lead pipe in which circulates a current of cold water. A centrifugal pump, also of lead, raises the liquid to the tank, and it thus circulates in a continuous manner until its strength reaches 0.7 to 1.0 per cent of chlorine. An apparatus of this type consumes 112 volts and 114 amperes, or 19 horse power, and gives in three hours 90 gallons of a solution containing 0.85 per cent of chlorine, representing 12 pounds of active chlorine.

The Current Supplement.

The current SUPPLEMENT, No. 1328, is begun by an article on M. Berthelot, accompanied by an engraving, showing the great chemist in his laboratory. "The Hospitals of Japan" is a very instructive article. "Low Grade Gold Mining and Milling" is accompanied by illustrative diagrams. "Electrically Operated Radial Drills" shows several new types of machine tools. "Animal Change and Environment" is by Prof. Thomas H. Montgomery. "Animals that Clothe Themselves" is an interesting entomological article. "Syntonic Wireless Telegraphy" is by Guglielmo Marconi. "Germany's Machinery Trade in 1900" gives full statistics.

Contents.

(Illustrated articles are marked with an asterisk.)

Automobile news 375
Battery, storage 376
Brick carrier* 378
Bridge, new East River, floor system* 369, 374
Car-fender* 372
Cement for South Africa 372
Comet, Encke's, return of 371
Derailment damages a pond 375
Drydock, floating* 377
Electrical notes 375
Electrograph* 373
Engineering notes 374
Equipment, costly 370
Exposition St. Louis 371
"Georgia," wave line 370
Gun, Robinson Crusoe's 375
Hypochlorites, electrolytic apparatus 378
Meteor seen in daylight 375
Pump, self-measuring* 378
Ruling, patent right, new 375
Science notes 371
Scouts, naval, 25-knot 371
Station, power, greatest 370
Sun motors for India 375
Telephone station, Chinese* 376
Trade, machinery, German 370
Tunnel, rapid transit, to Brooklyn 370
X-rays, laws of absorption 370
Yacht "Lysistrata"* 372

© 1901 SCIENTIFIC AMERICAN, INC.

RECENTLY PATENTED INVENTIONS.

Agricultural Implements.

DRAFT-EQUALIZER.—EDWARD E. MAXON, Abbott, Neb. The draft-equalizer comprises a main beam on which three whilletree-carrying levers are independently mounted, a connection extending from each end of the middle lever respectively to the ends of the remaining levers. By these means the horses are hitched to a plow or harvester in such a way that all may work on unplowed ground, when a plow is used, and on stubble ground when a harvester is used.

DIVIDER FOR MOWING OR REAPING MACHINES.—JOHN M. CLARK, Rathbone, Mo. The invention provides improvements in devices for dividing the grass or grain at the end of a cutter-bar; and by its means short, long-standing, or fallen grass or grain is effectually divided without manually adjusting the device for varying heights.

Engineering Improvements.

VALVE.—WILLIAM F. MULLANEY, Marshall, Minn. This invention relates to a valve which is so constructed that it can be operated either by pressure applied directly thereto by sliding its stem, or by pressure applied by the action of a screw formed on the stem. In the former case the valve may be operated quickly, and in the latter case great force may be brought to bear on the valve.

MEANS FOR GOVERNING SUPPLY OF STEAM UNDER PRESSURE.—CICERO M. HOBBY, Iowa City, Iowa. The object of the invention is to provide a simple device in which the supply of steam or other fluid is cut off automatically as soon as a predetermined pressure is reached. The invention is applicable to engines, pumps and other apparatus, but is particularly suitable for the automatic supply and cut-off of steam in pumping-engines, in engines without gearing to produce circular or reciprocating motion, and for use where the boiler-pressure or live pressure is variable and skilled or regular attendance impossible.

Jars and Bottles.

TESTING-BOTTLE.—CONSTANTINE WAGNER, Manhattan, New York city. The inventor has devised a bottle for testing milk and other liquids, which bottle is arranged to permit one conveniently to make a test, and readily and accurately to read off the amount of fat without the use of dividers or like measuring tools. The column of fat is brought down in the graduated tube until the bottom is at zero. The height of the column of fat can then be easily read off without calculation or the use of a measuring tool.

NON-REFILLABLE BOTTLES. LUTHER A. MCCORD and JOHN D. ADAMS, Laurens, S. C. The valve-seat in the bottle-neck is normally closed by a ball-valve held to the seat by a weighted pendulous portion. A guard is provided which serves to deflect a wire inserted through the neck for the purpose of unseating the valve. An attempt to refill the bottle by means of a vacuum-pump is frustrated, for the reason that the ball-valve floats on the rising liquid and closes the valve-opening.

JAR-CLOSURE.—JOHN SCHIES, Anderson, Ind. This improved jar-closure is of simple construction, can be easily applied to the jar, and easily removed. To remove the closure it is necessary merely to take an ordinary table-knife and press back small points or teeth which hold the closure to the jar top. This releasing of the points or teeth is facilitated by their form.

JAR-CLOSURE.—JOHN SCHIES, Anderson, Ind. The neck of the jar is provided on its outer side with a downwardly facing shoulder. On this neck a cap fits. To secure the cap, a continuous unbroken ring is employed, having at its upper edge an inwardly-projecting flange overlying the outer edge of the cap and extending inwardly beyond the inner line of the external downwardly-facing shoulder. The body of the ring is fitted snugly around the neck of the jar and has at its lower edge, portions bent beneath the shoulder of the jar-neck and arranged to be bent outwardly to release the closure.

Mechanical Devices.

METAL-BENDING MACHINE.—CHARLES DECRETTE, Manhattan, New York city. The machine is designed to bend metal bars at a sharp angle at one operation with only one heating of the metal. Thus, much time and consequently much expense is saved, as compared with the bending-machines in which several heatings of the metal are required.

SAFETY GAS-LOCK.—CHARLES H. LEWEY, Chicago, Ill. The inventor has devised an improved safety gas-lock for the shut-off cock in a gas or other supply pipe. The lock is controlled by the key of the main entrance door to the factory, store, or other building in which the lock is located, so that the shut-off cock cannot be reached and opened until the door is unlocked; and the door cannot be locked until the shut-off cock is closed, for only then the key for closing the door can be removed from the gas-lock.

DUMPING-WAGON.—CHARLES CARROLL, General Delivery, Chicago, Ill. Mr. Carroll has provided a simple construction in which the body of the wagon is so hinged that it can be readily tilted into dumping position. A tilting rear-truck is secured to the body and connected with the forward truck by a hinged joint and by bars which extend rearwardly from the forward truck, means being provided whereby the hinge connection of the body and the axle of the rear truck may be caused to depart in order to dump the wagon.

SAWMILL-CARRIAGE.—BENJAMIN E. SERGEANT, Greensboro, N. C. This invention is an improvement in sawmill-carriages designed to hold the projecting ends of the rack-bar in a positive and certain engagement with the subjacent pinion by which it is driven. A more convenient, stronger, and practical construction of sectional log beam is also provided for the carriage.

ORE-PULVERIZER.—ALBERT C. CALKINS, Los Angeles, Cal. The patent describes a convenient and effective device for further reducing or pulverizing crushed ore before separating the precious metals which it contains. The machine is designed for the use of assayers and chemists. The device comprises a concave bed and an oscillating shoe having in its middle an opening leading to the space between the shoe and bed. The middle of the upper surface of the shoe is lower than its outer edges, and its outer edges are sharp. This construction permits the coarse particles to tumble over the sharp angle in returning to the middle of the shoe.

GYRATORY MULLER.—ALBERT C. CALKINS, Los Angeles, Cal. The distinguishing features of novelty in this invention are a hinged bail-shaped frame in combination with open grappling hooks on a rotating shaft, by which the parts may be quickly opened and separated. By reason of this construction the machine can be rapidly cleaned after finishing one laboratory sample, and before grinding another. The only adjustment necessary is the turning-back of the bail, the bifurcated and hook-shaped crank-arm being thereby separated from the pins of the box.

TOY PISTOL.—EARL T. ADAMS and JOHN E. SIMPSON, Portsmouth, Ohio. The pistol has a moving tape or strip with spaced percussion caps thereon. The construction is simple and durable. A large number of caps can be exploded in rapid succession without the slightest danger.

WASHING-MACHINE.—HENRY F. and ROBERT H. STAGGS, McKinney, Texas. These inventors have devised an improved washing-machine arranged for use on any kind of tub and adapted to insure a perfect, uniform washing of all the clothes in the tub by the use of yieldingly-mounted pounders which intermittently change their positions relatively to the clothes under treatment.

CENTRIFUGAL CLARIFIER.—FRANK H. RICHARDSON, Pueblo, Colo. The object of the invention is to provide a machine which centrifugally separates impurities from water or other liquids. The clarifier comprises a rotary cylinder around the inner side of which sediment-chambers are arranged. Valves control communication between the sediment-chambers and the interior of the cylinder. A vertically movable part produces vertical movements in the valve. The movable part is moved by gear-wheels driven by the rotary motion of the clarifier.

REVOLVING TRUCK FOR FLAGPOLES.—SYLVESTER S. MCGRATH and JOHN J. LAWLOR, Manhattan, New York city. The invention provides a truck capable of revolving upon a flagpole, on which a lightning-rod is used. The revolving truck serves to prevent the halyards from becoming entangled, and also serves to protect the halyards where they pass over bearings in the truck.

TELLURIAN.—AIDGAR A. HOYLMAN, Organcave, W. Va. The chief object is to produce a simple apparatus to enable a teacher to explain the fundamental facts of astronomy, such as the inclination of the earth's axis to its orbit; the rotation of the earth upon its axis; the alternation of day and night for different longitudes and latitudes for different seasons of the year; the revolution of the earth around the sun; the change of the seasons; the revolution of the moon around the earth, and its relation in time to the revolution of the earth around the sun; the conditions under which eclipses of the sun and moon occur, and other phenomena resulting from the relative motion of the sun, earth, and moon.

ROLLER-MILL FOR GRINDING AND CRUSHING.—JOHANNES C. WEGERIF, Leigh-on-Sea, Essex, England. With the ordinary hyperboloidal rolls, the obliquity of the roll-axes, necessitates the placing of one or both axes out of the horizontal plane, in consequence whereof an undue proportion of the pressure is borne by the bearing at the lower end of the roll, thereby very seriously affecting the efficiency of such rolls. The present invention obviates this evil, the axes of both rolls being perfectly horizontal.

SCREW-DRIVER.—GARY L. WOODRUFF, Albany, N. Y. The inventor has devised an improvement in screw-drivers in which the handle and shank are adapted for rotation when pressure is applied, so that a screw engaged by the bit is driven into the material. The novel features of the invention are to be found in a peculiar construction of bit which is so formed at its free end that it can be used for boring holes. Furthermore, a bit designed for drilling metal can be substituted for the wood-boring bit, thus increasing the range of utility of the instrument.

HALF-TONE NEGATIVE.—THOMAS S. FOX, Brooklyn, New York city. To avoid much of the hand or rule work which in photoengraving is slow and expensive Mr. Fox has devised a novel method of making a negative. The portions not to be reinforced are stopped out with gum; and the portion to be reinforced is inked. Thereupon the stopped-out portion is washed. Finally an opaque substance is applied to the ink to render the ink of the impression opaque. Variegated but extremely strong effects are produced in the final prints.

CABLE-GRIP.—CHARLES NOBLE, Sisson, Cal. The invention [illegible] improvements in cable-grips employed in hauling logs [illegible] The grip has but few parts and is not liable to get out of order. The construction is such that the simple act of hooking the device over a cable after the draw-dogs are fixed in a log causes it to grip the cable and remain fixed thereon until the draw-dogs are removed.

ACETYLENE-GAS APPARATUS.—OLIVER H. HAMPTON, Williamsburg, Ind. The gas-machine which has been devised by Mr. Hampton automatically generates gas in accordance with the amount consumed. The danger of the generator's bursting by overpressure is entirely obviated. Means are provided for automatically obtaining a uniform level in the generator. The carbid-holder is entirely submerged in an ample quantity of water, and therefore the gas is kept cool. Generation begins at the bottom and the gas is made to pass over the unused carbid which absorbs the moisture from the gas.

BORING-MACHINE.—SUMPTER L. HARWOOD, Faunsdale, Ala. The machine is a well-boring machine in which water is forced to the revolving drilling tool to assist in loosening the ground and to cause the loose material to flow up in the drill-hole. The rate of cutting can be regulated according to the nature of the soil without subjecting the drill to the weight of the pipe-line. The pipe-line and drilling-tool are prevented from dropping into a bed of quicksand, if such be encountered.

TOOL.—DANTON O. BRUNNER, Somerset, Ohio. The tool, as constructed in accordance with the provisions of this patent, is compact and may be used for many purposes. It is specially serviceable in a stable, or as an implement to be carried in a vehicle. A nut-wrench, a pincers, and an eyelet-punch are included in the tool.

STAMP-FIXING MACHINE.—ALBERT S. HEINTZ, 213 Thirteenth Street, Portland, Ore. The inventor has devised an automatic and perfectly operating device through the agency of which a stamp may be cut from a sheet or strip, moistened and secured upon an envelop, document, or package, by the movement of a single rod or lever.

Railway Contrivances.

JOURNAL-BEARING.—ELWOOD E. BENNER, Sargent, Neb. Mr. Benner has devised an improvement in the brasses employed in car-journal bearings. The invention provides means for lubricating the journal by the use of water, thus economizing in the cost of lubricant and at the same time cooling the journal by means of the lubricating agent.

JOURNAL-OILER.—FRED E. PARSONS, Marshall, Minn. This invention relates to a simple device designed to be placed in a journal-box to hold the absorbent packing yieldingly against the journal, and by the use of which a less amount of packing is required than is ordinarily necessary.

Miscellaneous.

CLASP.—ARTHUR N. LUNDBURG, Wayne, Neb. The clasp is adapted especially for application to suspenders to take the place of suspender-buttons and the usual loops which are employed to connect the suspenders with the buttons.

BED.—WILLIAM D. OLNEY, Stillwater, Minn. The bed is mounted on rollers so that it can be readily moved from place to place. The construction is such that the bed can be moved into engagement with a cabinet and folded out of operative position. By this construction all the merits of the folding-bed are retained without the danger of an accidental collapse.

DRINKING-GLASS HOLDER.—RUDOLPH METZ, Atlantic City, N. J. The drinking-glass holder comprises two straps adapted removably to embrace the glass. Each strap comprises a retractile spring which serves to hold the straps around the glass. A handle extends between and is connected with the straps. The holder is merely slipped over the glass, the spring serving to prevent the straps from slipping.

KEYBOARDS FOR TYPEWRITERS.—JUAN B. VIDAL, Havana, Cuba. The invention provides an improved arrangement of keys by which the attainment of great speed in writing is facilitated, and which enables an operator to write as much by touch as by sight, thus rendering the work easier. The keys are arranged in two sections, one for the right hand and one for the left, and in each section the keys are disposed in groups, one group for each finger.

HAMMOCK.—LOUIS A. WRIGHT, Aspen, Wyo. The hammock is made of leather strips and a series of loops extending longitudinally. The loops in a series are linked together, each loop embracing a step between the link ends of the loop. Thus constructed a hammock forms a very durable supporting surface and can be very easily folded.

TIMBER-HOOK.—GEORGE H. HITCHINGS and PATRICK L. LACHAPELLE, Hoquiam, Wash. The novel features of the invention are to be found in the arrangement of connecting-straps in pairs extending side by side; in lapping the joint plate and the hook bars on opposite sides; and in providing the drag device with side bars which extend on opposite sides of the hook-bars and of the joint-plate. The inventors are thus able to avoid all twisting of the joints and to brace the parts of the hook in the desired positions.

PUMP-CAP.—AUGUST GUSTAFSON, Cherokee, Iowa. The cap or cover for the pump-barrel is provided with an opening for the passage of the pump-rod. A yoke is located on the outer side of the cover and spaced therefrom. Between the cover and the yoke at opposite sides of the opening are separate blocks adjustable toward and from the opening. The yoke and cover can be pressed toward the pump-barrel. The pump-cap thus constructed can be conveniently applied to a new or old hand-pump or force-pump.

ELECTRIC-FIXTURE BASE.—JAMES W. SMITH, Brooklyn, New York city. The fixture-base is intended for use on flat surfaces and can be fastened closely to a wall without using a number of intermediate ungainly parts. In this respect the fixture differs from the ordinary insulating device which is designed for attachment to gas-pipes, and which when secured to flat surfaces requires the interposition of a separate base.

MEANS FOR SWAGING METAL DENTAL PLATES.—NORRIS C. LEONARD, McMinnville, Tenn. The purpose of the invention is to furnish devices which provide simple and effective means for swaging metal dental plates directly on a plaster model. Thus, a more accurately fitting plate is produced than is ordinarily possible, and thus the necessity of making counter-dies is obviated. The invention saves much time and labor and prevents the plate from being scarred.

FIRE-HOSE NOZZLE.—THOMAS F. BURKE, Engine Company 52, Van Cortland Avenue, Riverdale, New York city. The fire-nozzle is designed to supply both air and water. Air is first pumped by the fire-engine instead of water in order to drive away the heavy smoke and to enable a fireman to locate the blaze without danger of being suffocated. Then the water is turned on and the fire extinguished. One of the novel features of the invention is a distributer which discharges water in the shape of a circle 125 feet in diameter. The fine stream of water thus obtained is hurled to a distance equal to that of a large stream, in which respect the nozzle differs from ordinary hose nozzles. This device has been very successfully tried and will be adopted by the New York Fire Department.

SCABBARD.—GEORGE R. SIMMONS, French Gulch, Cal. The scabbard is a bowie or hunting knife scabbard. The sheath or scabbard commonly provided for the blade of a bowie knife is not adapted to receive the cross-guard plate of the handle. It thus often happens that the plate is caught by high grass or cane and the knife pulled out. The improved scabbard obviates this difficulty.

FRAME-LATCH FOR BAGS, PURSES, ETC.—LOUIS B. PRAHAR, Brooklyn, New York city. The invention is an improvement upon a similar device already patented by Mr. Prahar. The novel feature of construction is a locking device which is adaptable to a pocket-book frame. The members of a frame can be unfastened either by rocking the locking device in one or the other direction or by drawing the locking device outward. When relieved from tension the locking device is always in position to latch the members of the frame.

MUSICAL INSTRUMENT.—HENRY C. MARX, Linn, Kans. The instrument is of the zither type, and is provided with keys for striking certain of the strings to produce chords, while the melody is played on a certain number of open strings or on certain of the strings with which the keys are designed to engage.

CURTAIN-HANGER.—JOHN L. F. C. KOBER, Cincinnati, Ohio. Means are provided for hanging curtains securely and artistically without the use of cumbersome and unsightly devices such as the usual curtain poles and rings. The curtain is hung by means which are entirely obscured, thus making it possible to display ornamentation.

TRUSS.—HENRY H. GERHARDT, Nashville, Tenn. The truss is so constructed that the pads or supports can be adjusted vertically and laterally to and from each other, and also adjusted to and from the person in order to increase or decrease their pressure. Each pad is also independently adjustable. The body-belt by which the pads are supported coacts with an auxiliary belt adapted to hold the body-belt in position and prevent the adjustment of the pads from being disturbed.

Designs.

DISPLAY CARD.—HENRY HEININGER, Orange, N. J., and WILLIAM UNGER, Manhattan, New York city. The display card is a bachelor's display card of an amusing character.

HOOK.—AUGUSTUS BROCKELBANK, Ossining, N. Y. The hook is to be used in connection with an eye for garments and is formed in a novel manner to enable the eye to be readily gripped and readily released.

NOTE.—Copies of any of these patents will be furnished by Munn & Co. for ten cents each. Please state the name of the patentee, title of the invention, and date of this paper.

© 1901 SCIENTIFIC AMERICAN, INC.

Business and Personal Wants.

READ THIS COLUMN CAREFULLY.—You will find inquiries for certain classes of articles numbered in consecutive order. If you manufacture these goods write us at once and we will send you the name and address of the party desiring the information. **In every case it is necessary to give the number of the inquiry.**

MUNN & CO.

Marine Iron Works. Chicago. Catalogue free.

Inquiry No. 814.—For manufacturers of type foundry machines.

For hoisting engines. J. S. Mundy, Newark, N. J.

Inquiry No. 815.—For latest machine for making spring mattresses; also for all-cotton-and-husk mattresses with cotton top.

TURBINES.—Leffel & Co. Springfield, Ohio, U. S. A.

Inquiry No. 816.—For typewriter ribbons before they are inked.

"U. S." Metal Polish. Indianapolis. Samples free.

Inquiry No. 817.—For hair cloth to be used in absorbing oil on machinery.

WATER WHEELS. Alcott & Co., Mt. Holly, N. J.

Inquiry No. 818.—For a motor about 1-6 horse power wound for 110 volt alternating current.

Yankee Notions. Waterbury Button Co., Waterb'y, Ct.

Inquiry No. 819.—For first class machine to apply, with two wires, solid rubber tires to vehicle wheels.

Machine chain of all kinds. A. H. Bliss & Co. North Attleboro, Mass.

Inquiry No. 820.—For a knitting machine with four or six needles.

Handle & Spoke Mchy. Ober Mfg. Co., 10 Bell St., Chagrin Falls, O.

Inquiry No. 821.—For plaiting machines for plaiting silk braid.

Sheet Metal Stamping: difficult forms a specialty. The Crosby Company, Buffalo, N. Y.

Inquiry No. 822.—For a firm engaged in cutting tinfoil letters from metal letter dies.

Sawmill machinery and outfits manufactured by the Lane Mfg. Co., Box 13, Montpelier, Vt.

Inquiry No. 823.—For telephones suitable for operating an exchange.

For Sheet Brass Stamping and small Castings, write Badger Brass Mfg. Co., Kenosha, Wis.

Inquiry No. 824.—For manufacturers of pressed wrought steel baskets (one-half bushel).

Rigs that Run. Hydrocarbon system. Write St. Louis Motor Carriage Co., St. Louis, Mo.

Inquiry No. 825.—For manufacturers of fans for cooling purposes run by a spring.

Ten days' trial given on Daus' Tip Top Duplicator. Felix Daus Duplicator Co., 5 Hanover St., N. Y. city.

Inquiry No. 826.—For the present address of the manufacturers or dealers in "The De Muth Dough Kneader and Beaten Biscuit Machine."

SAWMILLS.—With variable friction feed. Send for Catalogue B. Geo. S. Comstock, Mechanicsburg, Pa.

Inquiry No. 827.—For a list of manufacturers of oil filters.

Wanted—Punch and Die Work, Press Work and light Manuf'g. Daugherty Novelty Works, Kittanning, Pa.

Inquiry No. 828.—For a machine to sew with linen thread an article made of fine tempered tinned wire.

Machine Work of every description. Jobbing and repairing. The Garvin Machine Co., 149 Varick, cor. Spring Sts., N. Y.

Inquiry No. 829.—For a soldering-flux for soldering aluminium.

The celebrated "Hornsby-Akroyd" Patent Safety Oil Engine is built by the De La Vergne Refrigerating Machine Company. Foot of East 138th Street, New York.

Inquiry No. 830.—For manufacturers of fire apparatus for a village.

The best book for electricians and beginners in electricity is "Experimental Science," by Geo. M. Hopkins. By mail, $4. Munn & Co., publishers, 361 Broadway, N. Y.

Inquiry No. 831.—For machines for making seamless tin boxes.

WANTED—Partner to furnish money for patenting a useful invention. For particulars address A. Paul, 650 Third Ave., Brooklyn.

Inquiry No. 832.—For parties to make a special steel gauge.

Wanted an expert Asphalt Mining Engineer to accompany me to Mexico at once. Address C. & Y., 31 Nassau Street, N. Y.

Inquiry No. 833.—For manufacturers of small aluminium castings.

Position as Supt. by a practical Mechanical Engineer capable of handling men to a good advantage and reducing costs by labor-saving devices. Will purchase an interest in a reliable concern. C., Box 773, N. Y.

Inquiry No. 834.—For manufacturers of acetylene gas plants for lighting cities.

WANTED—Salesmen, also Engineers, to use and handle a fine specialty required by steam plants. Good pay and satisfaction guaranteed. Outfit free. Write for full particulars. Give home address. H. C. Myers & Co., 100 River Street, Cleveland, O.

Inquiry No. 835.—For manufacturers of pure Banca tin and genuine hardening.

Valuable Patents For Sale—The following patents, to wit: (1) Cork-screw, (2) Combination Lock, and (3) Locking Stop Cocks for trains using the Air Brake System. Must be sold at once, in order to settle estate of patentee, who is now dead. Excellent patents. Apply to undersigned for information.

L. J. LAWRENCE, Administrator,
Murfreesboro, N. C.

Inquiry No. 836.—For miscellaneous tools and supplies for beet sugar factories.

☞ Send for new and complete catalogue of Scientific and other Books for sale by Munn & Co., 361 Broadway, New York. Free on application.

Inquiry No. 837.—For a 100 horse Corliss engine of special dimensions.

Inquiry No. 838.—For small belt-driven power hammer with blow of 75 pounds and stroke of 10 inches.

Inquiry No. 839.—For manufacturers of pneumatic springs for railway coaches and other vehicles.

Inquiry No. 840.—For novelties for the mail order business.

Inquiry No. 841.—For a "Gill" plant for extracting sulphur.

Inquiry No. 842.—For appliances for refining sulphur and for grinding "virgin rock" sulphur, also for sifting and producing ground sulphur (flour sulphur).

Inquiry No. 843.—For telegraph operators.

Inquiry No. 844.—For parties to manufacture a gas lamp made of sheet brass and galvanized iron.

Inquiry No. 845.—For dealers in an attachment to be applied to gas pipe to cause the gas to flow through a tank of gasoline.

Inquiry No. 846.—For cider-making machinery.

Inquiry No. 847.—For machinery for manipulating coffee, maize, sugar, etc.

Inquiry No. 848.—For apparatus to compress sulphurous acid gas commercially.

Inquiry No. 849.—For cutters of hard gray felt.

Inquiry No. 850.—For punching machinery for punching out mittens by means of dies.

Inquiry No. 851.—For manufacturers of patent ladies' glove fasteners.

Inquiry No. 852.—For manufacturers of fancy leather.

Inquiry No. 853.—For manufacturers of refrigerating plants.

Inquiry No. 854.—For manufacturers of apparatus for burning petroleum in furnaces.

Inquiry No. 855.—For improved woodworking machinery.

Inquiry No. 856.—For manufacturers of small stationary boilers and engines.

Inquiry No. 857.—For manufacturers of tracing wheels.

Notes & Queries

HINTS TO CORRESPONDENTS.

Names and Address must accompany all letters or no attention will be paid thereto. This is for our information and not for publication.

References to former articles or answers should give date of paper and page or number of question.

Inquiries not answered in reasonable time should be repeated; correspondents will bear in mind that some answers require not a little research, and, though we endeavor to reply to all either by letter or in this department, each must take his turn.

Buyers wishing to purchase any article not advertised in our columns will be furnished with addresses of houses manufacturing or carrying the same.

Special Written Information on matters of personal rather than general interest cannot be expected without remuneration.

Scientific American Supplements referred to may be had at the office. Price 10 cents each.

Books referred to promptly supplied on receipt of price.

Minerals sent for examination should be distinctly marked or labeled.

(8206) The K. Pub. Co. ask: How can copper be mixed in Babbitt, if it can be done? A. Good Babbitt metal contains copper. If you wish to add more, use copper filings, put in the bottom of the crucible, Babbitt on top, and cover with common soda; melt and stir.

(8207) F. R. M. asks: Can ice on a pond have a temperature below 0° C.? Why or why not? A. Ice is a very poor conductor of heat. The water under the ice in contact with it is at a temperature of 0° C. at all times. Below that the water rises from 0° C. to 4° C. If the ice is sufficiently thick we see no reason to doubt that its upper surface may be even below 0° C. when the lower surface is at 0° C. 2. If the pond is frozen clear to the bottom, can the temperature of the ice go below 0° C.? A. Ice has a specific heat about one-half that of water; that is, it will cool twice as readily. After ice is formed it behaves like any other solid; it may be cooled far below its point of freezing, just as iron or lead can. A piece of ice lying in the air at 40° below zero comes to be itself 40° below zero, of course. We very often meet the idea that ice must remain at the freezing point. Why should it? 3. In the lower illustration on page 49, SCIENTIFIC AMERICAN, January 26, 1901, why is the load on the forward large driving wheel placed on the same side as the coupling rod? Should it not be at the other end of the diameter? A. The counterbalance shown on the forward driving wheel is opposite to the driving crank on the inside, not shown. It is very light, and with the outside connecting rod counterbalances the inside driving crank and rod.

(8208) H. C. A. writes: In query 8068 F. L. asks concerning Avogadro's law and water. Is your reply correct, considered in the light of modern chemistry? No allowance has been made for the degree of electrolytic dissociation of the H_2O molecules—$HLHO + H_2O$ is not apparently considered, and you are probably aware that Avogadro's law never quite answered until the electrolytic dissociation factor corrected the error. A. The authority for the answer to which exception is taken was Remsen's "Chemistry," latest edition. Is there any better? We might cite also Lupke's "Elements of Electro-Chemistry," Walker's "Introduction to Physical Chemistry," Speyer's "Text-Book of Physical Chemistry" to the same purport. Nor does it seem that the discovery of electrolytic dissociation can have any bearing on the truth or falsity of Avogadro's hypothesis, since electrolytic dissociation was active and a fact when Avogardro discovered the statement which bears his name. Avogadro's law was inclusive of all the facts of the case, known or unknown.

(8209) A. D. asks: Can I convert a spark coil into an induction coil, and how? A. It is not advisable to try to convert a spark coil into an induction coil. You would better start new and make an induction coil. Our SUPPLEMENT No. 1124, price ten cents, describes one which gives a spark 6 inches long. Bonney's "Induction Coils," price $1, by mail, contains plans for coils of a variety of sizes.

(8210) L. L. C. asks for a solder for aluminium. A. A good solder for aluminium is an alloy of 50 parts cadmium, 20 parts zinc, 30 parts tin. Another: 45 parts tin, 10 parts aluminium. In alloys of cadmium and aluminium 15 to 30 per cent of cadmium has been used for solder.

(8211) J. H. L. writes: A friend and myself are interested in the telephone and we would like to know what the Ader receiver and relay are, or are there any other apparatus by Ader? On these points we would like to have more information. Where can we get it? A. The Ader transmitter is a multiple transmitter, and the Ader receiver is a bipolar receiver. They are described in Miller's "American Telephone Practice," price $3 by mail, a book which should be in the hands of every student of the telephone.

(8212) M. F. K. asks: 1. Can you give a rule for figuring the way to build transformers, i.e., the number of turns, size of wire, etc., for any current? A. The designing of a transformer for any current cannot be covered by a single rule. There are other factors to be taken into account besides the ordinary resistance. We can recommend Kapp's "Transformers for Single and Polyphase Currents," price $1.75 by mail. 2. When resistance is put in a circuit does it reduce the amperage proportionately as the voltage? A. Resistance added to the circuit of a direct current reduces the amperes, but not proportionately to the added resistance. The current follows Ohm's Law, $C = E/R$. R is the sum of all the resistances of any sort in a circuit. The added resistance is only a part of the total resistance, and the amperes should be figured from the resistances and the volts. The total voltage has no dependence upon the resistance. The rate of drop of voltage between two points on a circuit does vary as the resistance between those points. In alternating current circuits another factor is added to the problem, namely, the self-induction of the circuit. So that the apparent resistance of an alternating circuit is greater than its ohmic resistance. See chapter on alternating currents in Thompson's "Elementary Lessons," price $1.40 by mail. 3. Is a Daniell battery the best for general purposes and what are its faults for general uses? A. The Daniell's cell is not much in use at the present time. It has been superseded by the gravity cell, which has exactly the same elements and materials, except that no porous cup is used. For this reason the internal resistance of the gravity cell is less than that of the Daniell's cell. Its great value lies in the steadiness of the current it gives, because of its complete depolarization, so that it may remain in circuit throughout its life; its fault, if that term is admissible, is the small amount of current given. 4. How can I make a voltmeter with a fine compass and some No. 36 double-covered copper wire? A. A voltmeter is a galvanometer whose scale is marked in volts by comparison with a standard. Make your galvanometer and graduate it by some one's voltmeter. We should not advise a voltmeter made with a compass as an index. A coil of wire to swing in a magnetic field is the usual form employed. See SUPPLEMENT No. 1215, price ten cents.

(8213) I. S. W. asks: 1. Why will the earth act as return on a long circuit and will not do so on a short one? A. The earth will act as a return for a short circuit as well as for a long one, provided the ground is as good in one as in the other. 2. What is the voltage of the smallest shunt-wound dynamo used for lighting purposes, under the same conditions as enumerated on page 134, SCIENTIFIC AMERICAN, May 2, 1901? What size wind-mill would be required to run the above dynamo? 2. The ordinary voltage of incandescent lamps is from 52 to 115, and the dynamo must furnish the voltage of the lamps plus the drop in the line. The windmill in the account referred to had a wheel 35 feet in diameter and a sail area of 90 square yards. 3. Have thermo-electric piles been built giving 1 to 2 volts? A. Yes.

(8214) C. R. H. asks: Would ebonite be suitable for the plates of a Wimshurst machine? A. Yes.

INDEX OF INVENTIONS

For which Letters Patent of the United States were Issued for the Week Ending

June 4, 1901,

AND EACH BEARING THAT DATE.

[See note at end of list about copies of these patents.]

Acetylene generator, E. R. Angell 675,461
Acid and making same, derivative of oxycarbonic, A. Eichengrun 675,544
Acid, apparatus for making nitric, C. Uebell 675,760
Air brake, C. A. Ball 675,870
Alarm. See Burglar alarm.
Alarm device, safety, L. Da Rozir 675,871
Aluminium plating, A. G. Betts 675,584
Amalgamating apparatus, A. Lavoix 675,660
Anchor, W. S. Bickley 675,552
Anchor, F. Baldt, Sr. 675,705
Armature and magnet adjusting device for relays or other electric instruments, U. G. Rogers 675,675
Armature ventilation, F. A. Merrick 675,518
Armor plate, T. Hardie 675,511
Atomizer, A. Clarkson 675,556
Auger, miner's, J. Deemer 675,720
Automobile, R. B. Fageol 675,379
Automobile gearing, H. H. Buffum 675,620
Bag or sack, J. Sansone 675,415
Baling press, P. K. Dederick 675,439
Banana shipping case, F. Schmitz 675,641
Barrel filling and closing device, H. Kraemer 675,565
Battery cell, galvanic, C. T. Sittig 675,419
Battery tray, J. R. Blackwell 675,708
Bearing, ball, A. Bolzani 675,505
Bearing, roller, G. E. Bartholomew 675,618
Bearing, velocipede, G. E. Bartholomew 675,617
Bed, folding, H. McDonnell 675,519, 675,520
Beer cooler, E. Otten 675,790
Beet topping and pulling machine, sugar, U M. Fox 675,473
Bell, bicycle, S. Cooper 675,817
Bell mechanism, electric, W. E. Foster 675,653
Belt, driving, H. C. Capel 675,838
Bicycle battery casing, motor, R. M. Keating 675,390
Bicycle frame, R. M. Keating 675,391
Bicycle frames, joint for detachable, J. H. Barry 675,765
Bicycle lock, Russell & Brown 675,676
Bicycle, motor, R. M. Keating, 675,387 to 675,389, 675,393
Bicycle, motor, E. Y. White 675,458
Binder elevator, A. M. Allen 675,703
Binding, skirt, A. M. Weber 675,691
Boiler flue cleaner, steam, H. Rasmussen 675,673
Boot or shoe cushion tread, M. Bray 675,619
Bottle decanting apparatus, T. E. Lane 675,779
Bottle jacket, safety, G. M. De Waters 675,509
Bottle, non-refillable, W. L. Nottingham 675,670
Brake retainer, automatic driver, W. T. Simpson 675,864
Branding machine, P. Sherrer 675,642
Brick and tile cutting machine, E. M. Freese 675,825
Brick handling apparatus, J. P. B. Fiske 675,560
Bricks, apparatus for use in the manufacture of, J. P. B. Fiske 675,559
Brine, purifying, G. N. Vis 675,686
Brush, air, C. Phillips 675,840
Brush, magnetic, J. B. Righter 675,527
Buckle, suspender, Neuberger & Cleary 675,754
Buggy top support, E. H. Mason 675,549
Building block, A. Czepull 675,374
Burglar alarm, J. W. Rosengren 675,570
Burial casket, W. J. Shaw 675,679
Burner. See Gas burner.
Cake beater, E. Metz 675,836
Calcium carbid, producing, Zimmerman & Prenner 675,646
Camera, photographic, J. E. Thornton 675,454
Camera, photographic, W. D. Macdonald 675,781
Canceling and postmarking machine, stamp, W. P. Cheatham 674,814
Cap, I. Pachner 675,839
Cap or head covering, J. Doniger 675,852
Capsule filling apparatus, J. G. Gilmer 675,775
Car brake, electric, F. C. Newell 675,667
Car brake, hydraulic, J. H. Neal 675,837
Car draft and buffing appliance, S. D. Wright 675,579
Car fender, C. W. Adams 675,580
Car fender, street, G. A. Parmenter 675,523
Carbureter, R. S. Lawrence 675,566
Carbureter, explosive engine, T. L. & T. J. Sturtevant 675,424
Carbureter oil distributer, W. E. McKay 675,666
Carriages having axial recoil, hydraulic controller for, A. Kampf 675,386
Cart, push, B. Butler 675,541
Celluloid covered article and process of covering same, E. Stoeffer 675,451
Chain and sprocket guard, D. L. Thomas 675,502
Chart, adjustable, J. S. Baughman 675,537
Check blank, L. E. Francis et al 675,381
Check, safety, W. H. Black 675,766
Chenille fabric, woven, T. Hirst 675,734
Churn, A. Haworth 675,598
Cigar, M. Reinstein 675,756
Cigar wrappers, apparatus for manipulating, O. Hammerstein 675,442
Cigar wrappers under tension, cutting and storing, O. Hammerstein 675,441
Circuit breaker, automatic, C. E. Starr 675,865
Clock, calendar, Wejrostek & Wiedemann 675,763
Clock train, C. R. Arnold 675,582
Clothes wringer, A. G. Carling 675,813
Clutch and reversing mechanism, J. Blum 675,709
Coating fibrous material with metal, J. H. Robertson 675,413
Cock, gage, J. F. McCanna 675,665
Cock, gage, W. Muller 675,752
Collapsible tube, R. Brooks 675,372
Composing and justifying matrices and casting types therefrom, apparatus for, H. J. S. Gilbert-Stringer 675,829
Concentrator, E. A. Sperry 675,799
Contact plug, C. Wagner 675,690
Conveyor loading device, J. C. Hoshor 675,657
Conveying granulated materials, apparatus for, K. Frohnhauser 675,382
Corn sheller, J. V. Stradley 675,452
Corset, S. G. McClain 675,787
Cranes, equipment of electric, H. Burrell 675,811
Crate, berry picking, C. D. Warren 675,429
Crate for demijohns, etc., H. H. Higham 675,385
Cream separator, H. L. Minds 675,874
Culinary mixing utensil, J. B. Glover 675,475
Cultivator, B. F. Erway 675,592
Cultivator, J. H. Denison 675,721
Cultivator, lister, I. A. Weaver 675,431
Curtain or shade fixture, window, P. G. Emery (reissue) 11,912
Cutting tool, A. Contois 675,649
Cycle pedal brake and controller, motor, R. M. Keating 675,392
Dental chair elevating or lowering device, F. Ritter 675,674
Desk, hotel register, H. Hatch 675,443
Diethylcarbinolurethane and making same, O. Bonhoeffer 675,538
Disintegrating machine, B. Moustier 675,751
Dispensing can, B. G. Devoe 675,820
Display box, easel, H. W. Hildebrand 675,733
Display rack, ceiling, F. Marquart 675,861
Door hanger, H. E. Walradt 675,762
Dust collector, O. M. Morse 675,397
Drafting apparatus, G. Buchberger 675,767
Drier, M. E. Bingaman 675,808
Drying apparatus, G. A. Muenzenmaier 675,606
Drill. See Expansion drill. Rock drill.
Drilling machine, W. D. Richete 675,841
Dye and making same, anthraquinone, Schmidt & Jakobi 675,573
Dye and making same, anthraquinone, Schmidt & Tust 675,574, 675,575
Dye and make same, black sulfur, M. Boniger 675,585
Dye and making same, blue anthraquinone, R. E. Schmidt 675,572
Dye and making same, yellow acridin, O. Nastvogel 675,568
Dye, azo, Israel & Kothe 675,629, 675,632
Easel support, O. D. Hartwell 675,731
Electric brake. F. C. Newell 675,668
Electric cut-out, automatic, Greenstreet & Selby 675,383
Electric light bulbs, apparatus for removing, F. H. Renard 675,640
Electric motor controller, Merrick & Stull 675,517
Electric switch, J. M. Andersen 675,614
Electric time switch, O. Springer 675,643
Electrical distribution system, L. B. Stillwell 675,532
Electrical impulses and signals and apparatus therefor, transmitting, G. Marconi (reissue) 11,913
Electrolytic cell, Merry & Noble 675,749
Elevator, K. Kionka 675,546
Embroidering machines, etc., reading and punching apparatus for, H. Hill 675,444
Engine muffler, H. M. Quick 675,498
Engines, electric igniter for explosive, W. H. Cotton 675,557
Engraving machine cutters, machine for grinding, C. W. Pashley 675,609
Expansion drill and reamer, W. Channon 675,465
Eyeglasses, G. P. Gehring 675,595
Eyes, device for tesing, C. F. Kantlehner 675,739
Fabric, C. Green 675,831, 675,832
Fan or pump, centrifugal, S. C. Davidson 675,375
Fare register, C. E. Pratt 675,410
Faucet, C. H. Sultner 675,426
Faucet, I. F. Long 675,548
Faucet, float operated, E. Randolph 675,791
Faucet, self-closing, J. W. Lyon 675,635
Feed water heater, J. W. Casey 675,553
Fence, I. M. Warner 675,504
Filter, electric water, Teter & Heany 675,802
Filter press plate, H. F. Cleveland 675,589
Fire box, J. Cour 675,623
Fire escape, A. Oakley 675,788
Fire extinguisher, chemical, J. B. McLaren 675,400
Fireproof construction, W. Orr 675,402, 675,403
Fireproof construction and hanger therefor, G. H. Kunneke 675,486, 675,487
Fireproofing and preserving wood, J. F. Geisler 675,826
Fish hook, B. Edgar 675,853
Fish trap, floating, G. Dean 675,508
Fluid pressure coupling, L. D. Woodruff 675,535

(Continued on page 381)

© 1901 SCIENTIFIC AMERICAN, INC.



"Star" Foot and Power Screw Cutting Automatic Cross Feed **Lathes**

FOR FINE, ACCURATE WORK

Send for Catalogue B.

SENECA FALLS MFG. CO.
695 Water Street,
Seneca Falls, N. Y., U. S. A.

ROTARY ENGINES.—ARTICLES ON this type of engine, giving many details and illustrations, are contained in SUPPLEMENT Nos. **1158, 1186, 1193** and **1309.** Price 10 cents each. For sale by Munn & Co. and all newsdealers.

ENGINE & FOOT LATHES. MACHINE SHOP OUTFITS. TOOLS AND SUPPLIES. CATALOGUE FREE. SEBASTIAN LATHE CO. 120 CULVERT ST. CINCINNATI, O.



FOR LIGHT AND MEDIUM WORK

this new 14 inch

B. F. BARNES

Upright Drill is several laps ahead of any other drill on the track. It will drill from 1/16 of an inch up to ¾ of an inch and is a strong, well built, durable tool.

It doesn't cost a whole lot either. Details are yours for the asking.

B. F. BARNES COMPANY, Rockford, Ill.

HOT BLAST
WATER JACKET FURNACES
FOR
COPPER ORES.
MATTE from SULPHIDES AT ONE OPERATION.
UNION IRON WORKS,
San Francisco, Ca'., U. S. A.



Send for Catalogues.

Telephones,

for Interior, Short Line, Intercommunicating and Hotel Work. Write us for prices, catalogue, etc., with testimonials and references. Estimates cheerfully furnished. Agents wanted.

THE SIMPLEX INTERIOR TELEPHONE CO.,
431 Main St., Cincinnati, Ohio.

DRY BATTERIES.—A PAPER BY L. K. Bohm, treating of open circuit batteries, historical dry batteries, modern dry batteries, Hellesen's battery, Bryan's battery, Koller's battery, and the efficiency of dry cells. With three illustrations. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, No **1001.** Price 10 cents. To be had at this office and from all newsdealers.

BY-THE-BYE, WHEN YOU BUY A BICYCLE

be sure and buy the best, and that means the

BUFFALO KING.

either "Racer" or "Special." The "Queen" is for a lady. No better built wheels on the market—every rider satisfied. Thoroughly up to date in improvements. All parts of best materials. Put together by skilled workmen. Prices, $35 and $40. Illustrated Catalogue free on application.

THE WM. HENGERER CO., Buffalo, N. Y., U. S. A.

WE TEACH YOU FREE
$5. to $10. PER DAY.
Gold, Silver, Nickel and Metal Plating.

At home or traveling, using and selling **Prof. Gray's Machines.** Plates Watches, Jewelry, Tableware, Bicycles, all metal goods. NO EXPERIENCE. Heavy plate. Modern methods. No toys. We do plating, make outfits, all sizes. Complete, all tools, lathes, materials, etc., ready for work. **The Royal,** new dipping process, quick and easy. **Write today.** Pamphlet, samples, etc., **FREE.**
P. GRAY & CO., Plating Works, CINCINNATI, O.

WORKS LIKE A CHARM.

Perfect satisfaction is experienced using our No. 5, 6 or 9 **Hand Pipe Threading and Cutting Machines.** Crank or ratchet power. Gears housed from dust. Chasers set by graduation to any size, can be released from threading while in motion, opened to permit pipe being cut, and instantly closed.

Send for Free Catalogue to
The Merrell Manufacturing Co., 501 Curtiss Street, Toledo, Ohio.

THE MIETZ & WEISS **KEROSENE and GAS Engine**



burns **KEROSENE** cheaper and safer than gasoline. Automatic, simple, reliable **No** electric battery or flame used. Perfect regulation. Belted or directly coupled to dynamo for electric lighting, charging storage batteries, pumping **and all power purposes.**

Send for Catalogue.

A. MIETZ,
128-138 MOTT ST., NEW YORK.
Markt&Co., London, Hamburg, Paris

$1 YEARLY FOR REPAIRS.

It has been found that it costs a trifle less than $1 per year to keep our **Hoisting Engines** in repair. That speaks well for their superior make and durability, doesn't it? There is no more economical or serviceable engine made for mines, quarries, docks, etc. Much cheaper than steam. Both friction and geared hoist 6 to 150 h.p.



Send for Catalog

Weber Gas & Gasoline Engine Co., P. O. Box 1114-a, Kansas City, Mo.

COMPLETE TOOL LIST



comprising those in use by every trade or profession, with market prices and discounts of same is

Montgomery & Co.'s Tool Catalogue.

Best book of reference in the world for tools of all kinds. 510 pages, illustrated, pocket size. By mail for **25c.**

MONTGOMERY & CO.,
105 Fulton St., New York City.

Fluid pressure regulator, D. C. & S. Y. Anderson, Jr.	675,704
Flushing tank, T. Mann	675,491
Food for animals, preparing, Hlawitschka & Drucker	675,656
Fuel, compound of matter for artificial, L Patry	675,639
Fuel economizer, E. H. Hovey	675,512
Furnaces, heat regulating system for hot-air, O. Kornreich	675,858
Furnaces, means for promoting combustion in boiler, L. Markey	675,782
Galley end lock, E. E. Vink	675,613
Game, J. Berkey	675,807
Game apparatus, G. T. Voorhees	675,456
Game apparatus, J. A. Harkrider	675,478
Game table, J. C. Schank	675,842
Garment supporter, A. E. Magoris	675,748
Gas burner, incandescent, H. Burkert	675,712
Gas generator, acetylene, A. Davis	675,376
Gas generator, acetylene, T. H. Duncombe	675,769
Gas generator, acetylene, A. H. Deike	675,819
Gas lighter, catalytic, W. H. Porter	675,524
Gas meter support, H. T. Holland	675,735
Gas motor engine, two stroke cycle, Schumm & Munzel	675,796
Gas service pipes, automatic cut-off for, C S. Folsom	675,510
Gases, apparatus for indicating the presence of dangerous, H. G. Prested	675,755
Gate, H. S. Miller	675,493
Gear, change or reversing, W. G. Wilson	675,433
Gear, change speed, O. Norling	675,669
Gearing for binder driving or other mechanism, changeable, T. Meyerhoff	675,550
Generator. See Acetylene generator. Gas generator.	
Gold saving apparatus, A. W. Lockhart	675,514
Grain conveyor, J. Clarke	675,815
Grain drill feed tube, W. H. Stevens	675,450
Grain separator beater and picker, J. E. Shavland	675,418
Grinder, mower knife, Martin & Campbell	675,446
Grizzly or screen for washing placer gravel, phosphate, etc., W. S. Russell	675,610
Guard, A. E. McCormack	675,399
Gun, spring, W. A. Wilkins	675,534
Hackling machine, E. Kornhuber	675,484
Hair or clipping animals, apparatus for cutting human, A. Martin	675,492
Hammer, C. H. Edmands	675,820
Harrow attachment, E. E. Voorhees	675,428
Harrow, farm, J. W. Barnard	675,536
Harrow tooth fastener, J. C. F. Schenck	675,611
Harvester, corn, Martin & Morgan	675,835
Harvesters, etc., conveyor apron for, J. H. Kramer	675,547
Hat brim notcher, G. H. Smith	675,844
Hat holder, W. H. Kimball	675,741
Hearing, device attached to hats to aid in, A. G. Zimmermann	675,700
Heater, J. B. Harrison	675,777
Heel, cushioned, H. F. Rooney	675,793
Hinge for water closet seats, A. Shwab	675,797
Hoists, valve device for pneumatic, R. A. Rutherford	675,528
Hook and eye, G. F. Brockway	675,437
Hoop fastener, T. J. Jones	675,856
Hose supporter, J. Lavigne	675,394
Ice machine, A. Peter	675,671
Index, ledger balances, V. C. Brock	675,436
Insulating pipes, J. M. McMahon	675,447
Insulator, Andersen & Anderson	675,615
Journal box adjustable support, J. L. Record	675,411
Journal box and adjustable bearing therefor, T. W. Green	675,596
Junction box, receptacle, and fixture, combination water-tight, A. E. Jahl	675,738
Knitting machine, Millholland & Lee	675,663
Knitting machine, Rutledge & Lee	675,794
Lace machine, F. T. Adams	675,701
Ladder, extension, step, and scaffold, M. J. Lewis	675,744
Ladder hook, J. D. Hatch	675,545
Lamp-chimneys from breaking, device for preventing, G. A. Loyd	675,747
Lamp, electric arc, D. Higham	675,599
Lamp guard, G. Galster	675,724
Lamp, vapor, J. M. Noel	675,638
Lamps, adjustable protecting device for electric, E. J. McAllister et al	675,398
Lamps, electric heater for electric glower, Van Vleck & Stevens	675,427
Lathe dog, G. F. Stowe	675,684
Lathe for turning irregular forms, H. Derrer	675,469
Lead by electrolysis, manufacturing white, J. B. Tibbits	675,455
Lead, electrolytic production of white, Chaplin & Halloran	675,555
Lead salts by electrolysis, manufacturing, J. B. Tibbits	675,455
Leather staking machine, G. A. Henry	675,732
Ledger, loose leaf, F. Korsmeier	675,485
Level, spirit, C. M. Verrill	675,503
Locomotive tender, Ryan & Johnson	675,795
Loom picker check, O. Chandronnait	675,717
Loom shuttle, J. C. Bryan	675,810
Loom warp stop motion, W. I. Stimpson	675,682
Mail box, C. P. Myer	675,753
Malt house, J. F. Dornfeld	675,470
Malt kiln furnace, J. F. Dornfeld	675,471
Map, kindergarten, E. A. Lamphier	675,488
Match making machine, E. H. Eisenhart	675,770
Mattress making machine, J. W. Morgan	675,750
Measuring device, cloth, G. W. Specht	675,759
Metal rolls, combined grinder and polisher for, G. Darrell	675,590
Metal shearing machine, J. Lanz	675,743
Methylethylcarbinolurethane and making same, O. Bonhoeffer	675,540
Methylisopropylcarbinolurethane and making same, O. Bonhoeffer	675,539
Micrometer, F. Ullmer	675,875
Milker, cow, R. D. Roth	675,414
Mill. See Quartz mill, Rolling mill.	
Mining machine, coal, O. Jacoby	675,737
Mining machine, water saving, F. Auser	675,583
Mixing machine scraper, C. F. Sliger	675,798
Moistener, envelop and stamp, W. B. Kendrick	675,483
Moistener, fountain, J. N. Crabb	675,818
Mop head and wringer, combined, B. W. Smith	675,449
Motor, C. J. Pollock	675,497
Motor, C. W. Steele	675,800
Motor, A. Benson	675,846 to 675,848
Motor, A. Levedahl	675,860
Movement cure apparatus, C. A. Scholder	675,678
Multiple cylinder engine, Pettee & McCutchan	675,494
Musical instrument, combined manually and mechanically actuated, R. J. Bennett	675,706
Musical instrument, mechanical, E. W. Applegate	675,551
Musical instruments, action for pneumatic, C. L. Davis	675,468
Nitronaphthalene derivatives, making, Zacharias & Bernhard	675,434
Nut, lock, O. C. Moore	675,664
Nut lock, A. Keen	675,740
Nut lock, C. F. Green	675,728
Oil cup, watchmaker's, W. Carrick	675,851
Ordnance, apparatus for limbering or unlimbering heavy, Paul & Sock	675,405
Oven, warming, Carter & Hausfeld	675,715
Oxy-aldehydes, derivatives of aromatic, A. Eichengrun	675,543
Panel, building, H. W. Beardsley	675,648
Paper, apparatus for bordering letter, H. G. Turner	675,803
Paper bag machine, H. E. Westervelt	675,805
Paper clip or holder, J. Vadler	675,761
Paper, wall, W. J. Fryer	675,654
Pavement or roadway, F. J. Warren	675,430
Pen, fountain, P. E. Wirt	675,698, 675,699
Penholder and pencil attachment, F. Rench	675,792
Photosculpture apparatus, W. A. C. Selke	675,417
Piano hammer, C. W. Pressley	675,525
Pick, E. H. Grim	675,626
Picture mounting, A. W. Engel	675,558
Pigments, apparatus for electrolytic production of, J. A. Yunck	675,459
Piling, metal sheet, G. W. Jackson	675,736
Pipe coupling, W. H. Hammon	675,730
Pipe stopper, G. B. Sidelinger	675,680
Pithy stalks, machine for operating upon, G. R. Sherwood	675,758
Pitman, J. R. Carter	675,716
Plane, divided, H. A. Verge	675,533
Plating rack retaining loop, S. Lowe	675,662
Plow fender, J. J. McManmon	675,448
Plows, adjustable heel scraper for, N. C. Harris	675,655

(Continued on page 382)

AUTOMOBILE PARTS.
IF YOU ARE BUILDING AN AUTOMOBILE, WE CAN SUPPLY YOU WITH PARTS AND FITTINGS.
IN OUR SEVEN FACTORIES WE MAKE RUNNING GEARS, TOOL STEEL BALLS, STEEL RIMS, STEEL STAMPINGS, CHAINS, SHEET STEEL AND FORGINGS.
ALL FOR AUTOMOBILE CONSTRUCTION
QUOTATIONS ON APPLICATION.
THE AUTOMOBILE & CYCLE PARTS CO.
CLEVELAND, OHIO.

Gas Engine IGNITER



Complete with spark coil, $12.00. The **Best Thing** on the **market.** Latest and most improved model.

Send for Circular.

Carlisle & Finch Co., 233 E. Clifton Av., Cincinnati, O.

A PLEASURE LAUNCH

Must have speed, combined with safe and reliable power; she must be built upon lines of grace and beauty. The "Recreation" covers these requirements. In its use you are tranquil in mind, body and estate, no fixing and figuring upon "her going." Minimum weight, maximum power, economy of maintenance. Throttle speed regulator. Write for circular "S."

WESTERN GAS ENGINE CO., - - MISHAWAKA, IND.

The "Wolverine" Three Cylinder Gasoline Marine Engine.

Write for catalogue.

The only reversing and self-starting gasoline engine on the market. Lightest engine for the power built. Practically no vibration. Absolutely safe. Single, double and triple marine and stationary motors from ¾ to 30 H. P.



WOLVERINE MOTOR WORKS,
Grand Rapids, Mich.

GASOLINE MOTOR CASTINGS

For MARINE, VEHICLE and BICYCLE MOTORS,
with Working Drawings.

LOWELL MODEL CO., 22 Wiggin St., Lowell, Mass.



LOZIER GAS ENGINES LAUNCHES

Three handsomest and most elaborate catalogues ever published, free on request.

THE LOZIER MOTOR CO.,
26 Water Street,
PLATTSBURG, N. Y.

Acetylene Safety

Is tenfold greater than with city gas when our generator is employed. It stops making gas immediately you stop using gas. Fourteen sizes, $15 to $1000. Write for our literature.

The COLT TRADE MARK Carbide Feed Generator

Is based on the only correct and approved system, that of feeding dry carbide in small quantities to a large volume of water. It is safe, simple, economical, practical and patented.

THE J. B. COLT COMPANY
21 Barclay Street, Dept. S, New York.
PHILADELPHIA. BOSTON. CHICAGO.
Criterion Stereopticons. Acetylene Search Lights.

THE BICYCLE: ITS INFLUENCE IN Health and Disease.—By G. M. Hammond, M.D. A valuable and interesting paper in which the subject is exhaustively treated from the following standpoints: 1. The use of the cycle by persons in health. 2. The use of the cycle by persons diseased. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, No. **1002.** Price 10 cents. To be had at this office and from all newsdealers.

THE JOHNSON ROTARY PUMP.

Simple of construction, positive in action, easy and quiet in operation. Especially adapted to pumping soap, oil, sugar, lard, glucose, acids, starch, glue, varnish, corn and water, malt, etc. Large sizes for irrigation.

Made as a belt or steam pump, or combination, or operated by electric motor or gasoline engine. Manufactured by



DAVIS-JOHNSON CO., Station V, CHICAGO, ILL.
95 Liberty St., New York City.

Send your business card for 160 p. 1900 catalogue.



NICKEL AND Electro-Plating
Apparatus and Material.
THE Hanson & VanWinkle Co.,
Newark, N. J.
136 Liberty St., N. Y.
30 & 32 S. Canal St., Chicago.

"Perfection" Air Mattresses
(TRADE MARK) (AND CUSHIONS)
FOR CAMP - YACHT - HOME - HOSPITAL.
NON-ABSORBENT, HYGIENIC, ODORLESS.
When deflated can be rolled into small package for storage or transportation.
Send for Illustrated Catalogue with Prices.
Mechanical Fabric Co. PROVIDENCE, R. I.

THE "QUEEN" DRAWING PENS.
SCIENTIFICALLY SHARPENED.

All Queen Pens are sharpened by experts who have had many years' experience in making and sharpening Drawing Pens. Only the finest English Steel is used in the Queen Pens, and they are hand-made and carefully tempered by our improved process. **QUEEN & CO., Inc.,** Mathematical, Engineering and Scientific Instrument Makers, **1010 Chestnut St., Philadelphia.**

HIGHEST EFFICIENCY
attained in the
STOVER GASOLINE ENGINE



The best is always cheapest. *Write for prices.*

STOVER ENGINE WORKS, FREEPORT, ILL.

THE AUTO-CARBURETTOR

made upon a new principle furnishes a reliable explosive mixture. No pump required. Uses any grade of gasoline with no waste. Especially adapted to automobile and cycle motors. Write us for prices and booklet on Carburettors. Gasoline and Steam Engines and Automobiles built to order and repaired. **THE AVERY & JENNESS CO.,** 60 So. Canal St., Chicago.



Letters copied while writing.

No press; no water; no brush; no work. Any ink; any pen; any paper. Our Pen-Carbon never smuts; our clip holds paper firm. Write with no extra pressure, and our **Pen-Carbon Letter Book** produces a *perfect* copy. For letters, bills, etc. Can be used anywhere. If your stationer does not keep it, write for *free* specimen of work. Address Department I.

PEN-CARBON MANIFOLD CO., 145-7-9 Centre Street, New York.



TELEPHONES SOLD OUTRIGHT.

All kinds of Telephone Apparatus. Absolutely guaranteed. Switchboards for large or small exchange.

Kellogg Switchboard & Supply Co.,
243 So. Green Street, Chicago, Ill.

GERE GASOLINE ENGINES

SIMPLEST BOAT ENGINES MADE
CABIN AND OPEN BOATS
ENGINE CASTINGS, BOAT FRAMES
NEW CAT FOR 4 STAMPS
GEO. M. GERE YACHT AND LAUNCH WKS. GRAND RAPIDS, MICHIGAN.

PROSPECTIVE BOAT BUYERS.



By constructing your boat from a set of my **Boat Building Materials** more than one-half the boat factory's price can be realized. Also economize freight 500 per cent. Launches, Sail and Row Boats, Gasoline Engines. *Catalog free.*

FRED MEDART, 3545 DeKalb St., St. Louis, Mo.

HOLD ON THERE!

Send 5c. for catalog of
Monarch Marine Gasoline Engines
¾ to 45 H. P. $200 up.
Grand Rapids Gas Engine & Yacht Co.,
Grand Rapids, Mich.

ELECTRIC AUTOMOBILE. — DIRECTIONS, with many illustrations, for making a complete machine from two bicycles are given in SUPPLEMENT No. **1195.** The motor and battery are also treated of in detail. Price 10 cents. For sale by Munn & Co. and all newsdealers.



ARTESIAN

Wells, Oil and Gas Wells drilled by contract to any depth from 50 to 3000 feet. We also manufacture and furnish everything required to drill and complete same. Portable Horse Power and Mounted Steam Drilling Machines for 100 to 1200 feet. Write us stating exactly what is required and send for illustrated catalogue. Address

PIERCE WELL ENGINEERING AND SUPPLY CO.
136 LIBERTY STREET, NEW YORK, U. S. A.

21,000 TON SHIPS.

There will soon be plying on the Pacific Ocean, between Seattle and the Orient, ships of 21,000 tons burthen. These are the largest ships ever built, and they will have a very large passenger as well as an enormous freight capacity.

The best way to reach Seattle from the East is via the

NEW YORK CENTRAL LINES

and their connections. Only six days from New York or Boston.

A copy of No. 21 of the "Four-Track Series," "Round the World in 60 days," will be sent free, post-paid, to any address, on receipt of a postage stamp, by George H. Daniels, General Passenger Agent, New York Central & Hudson River Railroad, Grand Central Station, New York.

© 1901 SCIENTIFIC AMERICAN, INC.

SHEET METAL NOVELTIES.
WE ARE PREPARED TO MAKE ARTICLES AND STAMPINGS OF ALL KINDS AND SIZES. TOOLS AND DIES MANUFACTURED ON CONTRACT. FURNISH US BLUE PRINTS OR SAMPLES AND GET ESTIMATES.
STANDARD STAMPING CO.
DEP'T R. BUFFALO N.Y.

THE HUB
will keep you posted on
Automobiles.
At news stands or by mail, 25 cents. Six months' subscription $1.00.
THE HUB,
Room 6,
24 Murray St., New York.



YOUR BICYCLE
May need a new crank hanger or higher gear. We can furnish crank hangers complete with cups and cones, to fit any wheel. Write us for full information.
The Avery & Jenness Co., 60 S. Canal St., Chicago, Ill.

AUTOMOBILE AND MARINE MOTORS AND TRANSMISSIONS.
FOR THE BEST WRITE TO
BUFFALO GASOLENE MOTOR CO.
10-20 BRADLEY ST. BUFFALO N.Y.

SOMETHING NEW
PUNCTURE PROOF
SELF-HEALING PNEUMATIC BICYCLE TIRES
ARE A SUCCESS. GUARANTEED
A $10 SET NOW FOR ONLY $4.75
NAILS, TACKS, GLASS, ETC WILL NOT LET THE AIR OUT.
REGULAR PRICE $10.00
But to advertise we will send one pair only for $4.75
EXPRESS PREPAID
When cash accompanies order.
WILL SEND C.O.D. IF YOU WISH
PATENTED
MADE IN CHICAGO ILL. SAVE MONEY AND TIME. BY THE VIM COMPANY NO TROUBLE NO DELAY
And you can thoroughly examine them before you pay a cent. If you are in need of tires, order at once, giving size you want, and we will send a pair of the best and most durable tires ever made.
Catalogue sent Free.
Vim Company CHICAGO ILL. COR. RANDOLPH & FIFTH AVE.
Mention SCIENTIFIC AMERICAN.

THE ELECTRIC HEATER.—A VALUable paper, with working drawings of various forms of the electrical heaters, including electric soldering iron, electric pad for the sick, etc. 6 illustrations. SCIENTIFIC AMERICAN SUPPLEMENT **1112**. Price 10 cents. For sale by Munn & Co. and all newsdealers.

WILLIAMS' SHAVING SOAP

SOLD EVERYWHERE
Sent by mail if your dealer does not supply you
Williams' Shaving Stick, - - 25c.
Yankee Shaving Soap, (Round or Square), 10c.
Luxury Shaving Tablet, - - - 25c.
Swiss Violet Shaving Cream, - - 50c.
Williams' Shaving Soap (Barbers'), 6 Round Cakes, 1 lb., 40c. Exquisite also for toilet.
(Trial Size) Williams' Shaving Tablet for 2c. stamp
" " " " Stick " 10c. "
The only firm in the world making a specialty of SHAVING Soaps
THE J. B. WILLIAMS CO., Glastonbury, Ct.
LONDON PARIS DRESDEN SYDNEY

Building Edition Scientific American

MONTHLY, $2.50 PER ANNUM.
SINGLE NUMBERS, 25 CENTS.

The BUILDING EDITION for 1901 is the handsomest magazine in the United States. It has many new and important features. Send 25 cents for the March number, and see the new departments. The illustrations and cover are more attractive than ever. Send for "Are You About to Build?" and be convinced.

NEW DEPARTMENTS.

Monthly Comment.
Interviews with Architects.
New Books.
New Building Patents.
Notes and Queries.
Digest of Current Articles.

MUNN & CO.,
Publishers, 361 Broadway, New York.

Pocketbook, handbag or the like, M. Vogelgesang	675,687
Polishing machine, rotary, J. McCahey	675,636
Powder, smokeless, E. H. Ford	675,472
Power generating, storing and transmitting apparatus, C. M. Johnson	675,778
Power transmitter, A. Benson	675,849
Pressure regulator, V. J. Emery	675,854
Printer's chase, P. Seipel	675,529
Printing press, W. Scott	675,499
Printing press, J. L. Firm	675,773
Printing, producing forms for, H. J. S. Gilbert-Stringer	675,828
Projectile, visibly traveling, D. C. Beaman	675,845
Propeller, C. E. Hall	675,477
Propeller, K. G. Johnston	675,563
Propeller ball bearing, screw, L. S. Gardner	675,474
Propeller, screw, J. P. Ducassou	675,722
Pump, P. F. Oddie	675,401
Pumping apparatus, E. M. Laing	675,859
Pumping jack, Clark & Ferguson	675,466
Punch, A. H. Randall, Jr.	675,526
Quartz mill, A. Ford	675,872
Rail joint, F. R. Coates	675,542
Rail joint, W. J. Austin	675,869
Rail joints, forming, W. J. Austin	675,868
Railway grader, E. McCann	675,637
Railway joint, method of and means for forming, W. J. Austin	675,867
Railway rail joint, D. O. Ward	675,578
Railway rail joint, J. L. Wood	675,645
Railway signal appliances, device for holding, H. E. Smith	675,576
Railway switch, L. J. Lindsay	675,489
Recorder. See Time recorder.	
Refrigerator, W. Bachner	675,764
Resistance coil, graduated, F. Comminge	675,373
Riveting machine attachment, W. L. Kellerman	675,482
Roadway, S. Whinery	675,694
Rock drill, C. T. Litchfield	675,490
Rocking chair, folding, M. L. Smith	675,420
Rolling chair, H. E. Weisgerber	675,693
Rolling mill, continuous, V. E. Edwards	675,591
Rotary engine, J. D. McFarland, Jr.	675,521
Rotary press, T. S. Grimes	675,776
Sacking device, C. F. & A. C. Jacobson	675,481
Sad iron, H. L. Meyer	675,605
Sad iron, Cooper & Felker	675,650
Salt, manufacture of, A. W. Lawton	675,445
Sash fastener, N. P. Chaney	675,621
Sash fastener, E. Bittner	675,809
Sash pull and picture hanger, H. W. Downing	675,440
Sawmill carriage attachment, J. H. Brown	675,506
Saw sharpening machine, W. H. Lucas	675,780
Scale, price denoting, D. Walker	675,457
Screw cutting machine, D. Lake	675,834
Screw wrench, F. Searle	675,416
Seal press, A. M. Pardi	675,404
Secondary battery, W. J. Buckley	675,587
Secondary battery, C. L. R. E. Menges	675,784
Seed drill tongue socket, W. Stephenson	675,530
Seed, treating cotton, J. C. W. Stanley	675,423
Seed, treatment of cotton, J. C. W. Stanley	675,422
Separator sieve, D. Lippy 675,745,	675,746
Sewing machine guide, A. W. Moller	675,785
Sewing machine guide, shoe, J. W. Meloon	675,783
Sewing machine looper mechanism, L. Onderdonk	675,789
Sewing machine rotary take-up, Brush & Borton	675,438
Shank piece cutting machine, J. Lewis	675,661
Sharpener, disk, W. E. Clark	675,816
Sheet metal vessels, etc., joint or seam for circular, C. F. Mendham et al	675,603
Shingling bracket, F. Ewing	675,625
Shirt bosom pressing machine, D. H. Benjamin	675,435
Shoe turning device, G. B. Gardner	675,725
Skate, roller, C. Fohr	675,824
Sleigh, F. S. Ramsey	675,569
Soda water fountain, P. De Lacy	675,651
Soldering apparatus, can, W. S. Case	675,507
Speed of rotating shafts, apparatus for indicating and recording, Kent & Gordon	675,564
Speed regulator, N. Nelson	675,608
Speed regulator for prime motors, A. Meuschel	675,604
Spinning and doubling machinery, G. H. Millward	675,396
Spinning machine stop motion, F. Haggas, Sr.	675,476
Spring. See Vehicle spring.	
Spring motor, Keller & Jackson	675,857
Sprinkler, W. M. Potter	675,672
Square, combination, E. Carlson	675,464
Stacker, hay, W. G. Danielsen	675,624
Starch, manufacturing thin boiling, C. B. Duryea	675,822
Steam, device for separating mechanical impurities from, M. M. Brophy	675,711
Steam engine, W. L. Silvey	675,681
Steam engine, T. W. Godwin	675,855
Steam generator, W. Mitchell	675,862
Steam generator and water heater, C. E. Dawson	675,719
Steam muffler, E. P. Gray	675,830
Stencil cutting machine, J. W. Munson	675,786
Stoker, automatic, J. MacCormack	675,516
Stool, folding camp, A. P. Burson	675,713
Storage battery, W. J. Buckley	675,588
Storage battery, G. W. Hough	675,600
Storage battery, electrical, W. J. Buckley	675,586
Stove, S. F. Shafer	675,843
Stove, cooking, J. Ruppert	675,571
Stove or range, cooking, G. E. Wilbur	675,432
Stove shelf, Carter & Hausfeld	675,714
Stoves, gas valve for hot blast, D. Baker	675,462
Straightening or bending apparatus, R. L. Ambrose	675,369
Street sweeper, J. M. Harr	675,561
Stretcher or emergency carrier, J. W. Pettee	675,409
Stump puller, I. M. Bethel	675,370
Sweetening and preserving, composition of matter for, M. Kroell	675,601
Swimming device, L. C. Whitcomb	675,695
Switch throwing device, A. Stinner	675,683
Table. See Game table.	
Table locking device, pedestal, E. Tyden	675,577
Target, G. Tyrell	675,804
Teaching musical scale construction, apparatus for, J. E. Forfar	675,723
Telegraph, printing, R. A. Fowden	675,380
Telegraph, writing, Pollak & Virag 675,495,	675,496
Telephone extension bell, V. J. Van Horn	675,685
Telephone, pay, C. E. Egan	675,378
Telephone speaking tube or like receiver, H. A. Cutmore	675,467
Telephone switchboard signaling device, H. C. Dodge	675,377
Textile machine clamp, Weichelt & Gadd	675,866
Thio-urea compound and making same, A. Israel & R. Kothe 675,628,	675,631
Thread holding and cutting device, S. W. Hart	675,479
Thread, spooled, M. B. Stiles	675,801
Threshing machine band cutter and feeder, C. A. Long	675,515
Tickets or checks at public pay windows, apparatus for issuing, E. March	675,395
Till and means for registering cash receipts, W. Evans	675,593
Till, money registering, W. Haynes	675,384
Time recorder, workman's, W. W. Kimball	675,659
Tin, preserve, Besse & Lubin	675,707
Tire, M. Holaubek	675,873
Tire clamp coupling, rubber, H. R. Auld	675,616
Tire, elastic, W. F. Williams	675,697
Tires to wheels, means for securing elastic, W. F. Williams	675,696
Tobacco pipe, F. W. Flint	675,594
Tobacco pipe, H. W. Comstock	675,768
Tobacco pipe cleaner, Van Horn & Losie	675,612
Tow line, G. F. Sturgess	675,453
Toy bank, O. A. Logan	675,602
Toy horse, F. Heinlin	675,480
Toy pistol, F. J. Ropp	675,412
Toys, stop motion for mechanical, A. D. Converse	675,718
Track for heavy vehicles, endless, C. Bonagente	675,710
Transfuser, Andersen & Grady	675,647
Trolley pole, C. Nicholson	675,522
Truck bolsters, slide bearing for, E. F. Goltra	675,727
Truck, railway carriage, J. Bragge	675,371
Trunk lock, J. G. Gadsden	675,774
Truss pad attachment, C. Donovan	675,821
Tuning button, A. J. Lang	675,742
Type casting and composing apparatus, H. J. S. Gilbert-Stringer	675,827
Typewriter desk, M. J. Hafgar	675,729

(Continued on page 383)



Write for Free Illustrated Book G.

The "Khotal" Blue Flame Oil Stove
(FOR HOME OR CAMP OR YACHT)
generates gas from common kerosene. It will boil a quart of water in two minutes and cook a dinner quickly. It can be regulated to any desired degree of heat. It has no wick and no asbestos substitute. It is strong, durable and ornamental, being made of brass of superior finish and excellent workmanship A child can operate it.
The "Khotal" costs little to buy and little to run. The combustion is perfect; no smoke, no smell, no soot deposit on pots and pans.
Picture shows smallest size. 8 ins. high, weight 5½ lbs. Price $3.75. Made in sizes large enough to cook a course dinner.
THE HYDROCARBON BURNER CO., 197 Fulton St., New York
Boston, Mass.: Globe Gas Light Co., 77-79 Union St.

Braddock Hydraulic and Steam Packing Co.
Braddock, Pa., U. S. A.
John C. F. Jones, Proprietor,
MANUFACTURER OF
Hydraulic and Steam Packing,
Including The "James" Hydraulic and Steam Hammer Packing, and John C. F. Jones' Patent "Unique" Packing. Universally used by the most prominent Steel Plants in the United States.
Sample for Export furnished on application.

1. Metallic Peg used in James Packing. 2. James Hyd aulic and Steam Hammer Packing.

BICYCLE TIRE REPAIRING.—THE Mending of Single Tube Tires.—A practical article illustrating the method of inserting patches and plugs with pliers and pluggers, together with rubber band plugging and the use of puncture bands. 9 illustrations. Contained in SUPPLEMENT **1102**. Price 10 cents. For sale by Munn & Co. and all newsdealers.

THE NEW BRISTOL COUNTER

Registers an accurate account of work done on printing presses, grain rallies, weighing, measuring and other automatic machines. Counts up to 1,000,000 and repeats automatically. Simple, accurate, durable. Special counters to order. *Send for circular.*
C. J. ROOT, Bristol, Conn., U. S. A.

We Sell, Rent, Repair and Exchange
Typewriters
We sell Tabulating Attachments.
We sell Typewriter Supplies.
We sell Typewriter Furniture.
We furnish Stenographers and Operators. . . . . .
Can We Serve You?
Wyckoff, Seamans & Benedict
327 Broadway, New York



DICKERMAN'S DURABLE DESKS
Don't buy until you get our catalogue—100 pages of money saving values.
AMERICAN STORE STOOL CO., 33 Howard St., New York

Does 12% Interest You?

If it does, we would be pleased to have you send us your name and address, that we may send you a booklet which will tell you all about "Jupiter Steel Castings" and the "Neal Duplex Brake," as well as giving you full information concerning the Treasury Shares in this company, a block of which is now offered for sale at par value, $5.00 per share.

For a year and a half quarterly dividends, at the rate of 12 per cent. per annum, have been paid on all the outstanding stock of this company, and this dividend rate will be increased as soon as we can enlarge our plant at Everett, Mass., to meet the needs of rapidly growing business. The plant which we now have at Everett cost us over $250,000, but it is not large enough.

We have just received an order from the Fore River Ship and Engine Company for over one million pounds of Jupiter Steel Castings to be used in the construction of the New Battleships "Rhode Island" and "New Jersey," which this company is building for the United States Government. An order like this should mean something to every careful and sagacious investor.

THE UNITED STATES STEEL CO.,
143 Oliver Street, BOSTON, MASS.



SALESMEN AND AGENTS WANTED
BIG WAGES—Our Famous Puritan Water Still, a wonderful invention—not a filter. 22,000 already sold. Demand enormous. Everybody buys. Over the kitchen stove it furnishes plenty of distilled, aerated drinking water, pure, delicious and safe. Only method. Distilled Water cures Dyspepsia, Stomach, Bowel, Kidney, Bladder and Heart Troubles; prevents fevers and sickness.
Write for Booklet, New Plan, Terms, etc. FREE
Harrison Mfg. Co., 297 Harrison Bldg., Cincinnati, O.

Acetylene Gas Lighting
Reduced to the most Efficient, Safest, Simple and Economical Use.
We guarantee our machines perfectly automatic in action, to extract all the gas from the carbide, and absolutely no over production or loss of gas. Approved by the various Boards of Fire Underwriters. Standard sizes 10 to 150 lights. Exclusive territory given to responsible agents. Correspond with



NIAGARA FALLS ACETYLENE GAS MACHINE CO.,
Niagara Falls, N. Y. and Canada.

SYNCHRONOGRAPH.—A NEW METHod of rapidly transmitting intelligence by the alternate ing current. A full description of the interesting apparatus of Crehore and Squier. 13 illustrations. SCIENTIFIC AMERICAN SUPPLEMENTS **1114** and **1115**. Price 10 cents each. For sale by Munn & Co. and all newsdealers. Send for new catalogue.

LEROY RACER
Is in every way a strictly up-to-date mount. It is one of the handsomest bicycles on the market and a pleasure to own one. We manufacture bicycles in every state of completion or complete from $25 to $35 and guaranteed for one year. Get our catalogue.



Address Bicycle Dept., John R. Keim, Buffalo, N. Y.

The Typewriter Exchange



1½ Barclay St., NEW YORK
124 La Salle St., CHICAGO
38 Bromfield St., BOSTON
817 Wyandotte St., KANSAS CITY, MO.
209 North 9th St., ST. LOUIS, MO.
432 Diamond St., PITTSBURGH, PA.
3 West Baltimore St., BALTIMORE, MD.
536 California St., SAN FRANCISCO, CAL.
We will save you from 10 to 50% on Typewriters of all makes. *Send for Catalogue.*



PERFORATED METAL
OF EVERY DESCRIPTION AND FOR ALL USES.
THE HARRINGTON & KING PERFORATING Co. 225 N. UNION ST. CHICAGO, ILL. U.S.A.

© 1901 SCIENTIFIC AMERICAN, INC.

The Search for Work

The man who can do something better than anyone else doesn't search for work. Employers search for him. We teach the theory of engineering and the trades to men already at work. Thousands of our students have secured a

Salary-Raising Education

in Mechanical, Electrical, Steam, Civil or Mining Engineering, Chemistry; Architecture; Plumbing; English Branches.

When writing state subject in which interested.

International Correspondence Schools, Box 942, Scranton, Pa.

ELECTRICAL ENGINEERING TAUGHT BY MAIL.

Write for our Free Illustrated Book. "CAN I BECOME AN ELECTRICAL ENGINEER?"

We teach Electrical Engineering, Electric Lighting, Electric Railways, Mechanical Engineering, Steam Engineering, Mechanical Drawing, at your home by mail. Institute indorsed by Thos. A. Edison and others.

ELECTRICAL ENGINEER INSTITUTE, Dept. A, 240-242 W. 23d St., New York.

GRAND PRIZE

PARIS 1900 - HIGHEST AWARD POSSIBLE.



When all other writing machines fail, the Smith Premier will still be serving you well, day by day, year by year. Because the

Smith Premier Typewriter

has a longer life of usefulness than any other machine. It is built right for long, hard, continuous service. Durability must be present in the Best Value Typewriter and that, emphatically, is what The Smith Premier is—the Full Value—Best Value Typewriter.

ILLUSTRATED CATALOGUE FREE.

The Smith Premier Typewriter Co. SYRACUSE, N. Y., U. S. A.

50 YEARS' EXPERIENCE

PATENTS

TRADE MARKS
DESIGNS
COPYRIGHTS &C.

Anyone sending a sketch and description may quickly ascertain our opinion free whether an invention is probably patentable. Communications strictly confidential. Handbook on Patents sent free. Oldest agency for securing patents.

Patents taken through Munn & Co. receive *special notice*, without charge, in the

Scientific American.

A handsomely illustrated weekly. Largest circulation of any scientific journal. Terms, $3 a year; four months, $1. Sold by all newsdealers.

MUNN & Co. 361 Broadway, New York
Branch Office, 625 F St., Washington, D. C.

Typewriting machine, J. F. Ames	675,806
Umbrella, folding, F. G. Chandler	675,554
Umbrella tip retainer, E. W. Groeschel	675,597
Urea compound and making same, Israel & Kothe	675,630
Urea derivative and making same, Israel & Kothe	675,627
Valve, W. J. Clinton	675,622
Valve for liquids, W. A. G. Schonheyder	675,757
Valve gear, explosive engine, W. G. Stolz	675,501
Valve gear, gas engine, G. Alderson	675,581
Valve, safety, C. H. Kaplinger	675,513
Vehicle, motor, F. O. Stanley	675,421
Vehicle, motor, T. L. & T. J. Sturevant	675,425
Vehicle, motor, A. L. Stevens	675,531
Vehicle spring, J. P. Larson	675,634
Vehicle steering device, motor, A. C. Stewart	675,644
Vessel, navigable, J. Campbell	675,812
Vine frame, A. Brunneder	675,850
Violin bow, C. W. Gaston	675,726
Wagon body scoop board, G. R. McGinnis	675,863
Wardrobe and bed or couch, combination, H. F. Adams	675,702
Watch guard, Kantrowitz & Goldberg	675,633
Water motor, A. Ferguson	675,772
Water regulating device, T. J. Sanford	675,677
Water tube boiler, H. D. Hubbard	675,658
Watering device, stock, N. Wehr	675,692
Weighing and weight printing machine, N. Nelson	675,607
Weighing machine, automatic, E. H. Eisenhart	675,771
Wire reeling apparatus, C. Hug	675,562
Wood chips, apparatus for assorting, N. M. Jones	675,833
Wood cutting machine, kindling, D. Levin	675,567
Wood seasoning, Ste. Marie & Hoffmann	675,500
Wool, apparatus for extracting fat from, G. Peltzer	675,407
Wool degreasing apparatus, G. Peltzer, 675,406,	675,408
Work benches, pneumatic lift for, Doebler & Cooper	675,652
Wrist pins and pistons, device for aligning, W. E. Boyce	675,463

DESIGNS.

Arch stone, M. M. Phipps	34,636
Badge, F. Koch	34,608
Belt strap, lady's, W. Rettenmeyer	34,611
Box, A. F. Wood	34,618
Buckle, slide, B. Fischman	34,610
Calendar, H. Doyle	34,603, 34,604
Candy mold, C. Repetti	34,617
Chair seat, H. B. Morris	34,619
Cigar, M. Reinstein	34,602
Clock case, L. A. Cloon	34,605
Clothes washer, steam, G. Shank	34,629
Collar, A. M. Shauck	34,614
Corn parer, A. Weller	34,606
Fork, W. Hathaway	34,607
Garment supporter, E. L. Merrill	34,612
Gem setting, solitaire, C. T. Wittstein	34,609
Glass tray, R. Haley	34,620
Hat, straw, J. R. Paine	34,613
Heel die, F. E. Wright	34,625
Lathe steady rest frame, J. J. McCabe	34,628
Lathe tail stock frame, J. J. McCabe	34,627
Punching bag support, G. S. Maxwell	34,623
Railways, track or way for amusement, H. Morris	34,633 to 34,635
Sash lock, H. T. Henderson	34,626
Shaft iron, buggy, H. P. Koster	34,631
Shoe and flexible gaiter, I. B. Urquahart	34,616
Soda water glass holder, J. J. McLaughlin	34,621
Vehicle running gear, motor, H. L. Warner	34,632
Vest or similar article, A. Lang	34,615
Warp stop motion detector, W. I. Stimpson	34,624
Water receptacle, C. W. Meinecke	34,622
Wire tightener, J. C. Elder	34,630

TRADE MARKS.

Bakery products and confectionery, certain named, National Biscuit Co.	36,521
Bitters, California Fruit Extract Co.	36,527
Boots and shoes, Gale Shoe Manufacturing Co.	34,514
Camera shutters, Rochester Optical & Camera Co.	36,519
Cigars, M. R. Cords	36,526
Cosmetics, S. J. Allen	36,531
Elestic web, suspenders, and dress bindings, H. B. Claflin Co.	36,504
Fabrics, certain named, G. Willis	36,507, 36,508
Fibrous materials, certain named, Norddeutsche Wollkammerei & Kammgarnspinnerei	36,506
Filters, certain named, General Engineering Co.	36,542
Hats, men's and boys', Joseph Pfeifer Clothing Co.	36,503
Knives, razors and scissors, H. Clauss	36,518
Matches, friction, Diamond Match Co.	36,525
Musical instruments, automatic playing attachments for, Ludwig & Co.	36,540
Musical instruments, pneumatic attachments for, Roth & Engelhardt	36,541
Objectives, Bausch & Lomb Optical Co.	36,520
Paint, Akron Mining, Milling & Manufacturing Co.	36,539
Pillow tops, Sondheim & Magnus	36,543
Remedies for certain named diseases, T. M. McWhorter	36,536
Remedies, headache, Butts & Pote	36,533
Remedies, proprietary, W. R. Buchanan, 36,537,	36,538
Remedy for a certain named disease, Cook Remedy Co.	36,535
Remedy for certain named diseases, E. C. Scott	36,534
Salve, corn, Stauff & Foster	36,532
Sheetings and drills, Brandon Mills	36,509
Sheetings and drills, Camden Cotton Mills	36,510
Sheetings and drills, Easley Cotton Mills	36,511
Sheetings and drills, Pelzer Manufacturing Co. 36,512,	36,513
Shoe polish, O. F. Palmer	36,529
Shoes, ladies', Lindner Shoe Co. 36,515 to	36,517
Starch, certain named soluble, E. Schaal, a Firm 36,522,	36,523
Steam and gas engines and their parts and accesories, Crest Manufacturing Co.	36,544
Sulfur, Catton, Bell & Co.	36,524
Toilet preparation, H. Kettler	36,530
Tonics, R. J. Sarasy	36,528
Underwear, Mohawk Valley Cap Co.	36,505
Works of art and publications, certain named, W. F. Osborne Co.	36,502

LABELS

"Cedar Rapids," for meats, A. von Cozhausen	8,427
"Dr. A. A. Bigelow's Pain Annihilator," for a medicine, M. L. Bigelow	8,435
"Eau Dentifrice des Elegantes," for a dentifrice, E. Glasse	8,434
"Fidelity," for meats, A. von Cotzhausen	8,428
"Flexible Starch," for starch, National Starch Co.	8,430
"German Antiseptic Wonderoil," for an antiseptic oil, Johnson Drug Co.	8,438
"Lober's Fine Biscuit Specialties," for biscuits, J. G. Lober & Co.	8,429
"Lyfe's Oneder," for a medicine, S. L. Sparks	8,436
"Old Hickory Rye," for whiskey, P. Goldberg	8,432
"Red Cross White Oil Liniment," for a liniment, Albany Chemical Co.	8,437
"Roachell," for an insecticide," Danbury Sanitary Co.	8,439
"Tisapure Rye Whiskey," for whiskey, E. Rafter	8,433
"Zeigler's Effervescent Tablets," for effervescent tablets, G. Zeigler Co.	8,431

PRINTS.

"Lewis' Single Binder," for cigars, F. P. Lewis 353

A printed copy of the specification and drawing of any patent in the foregoing list, or any patent in print issued since 1863, will be furnished from this office for 10 cents. In ordering please state the name and number of the patent desired, and remit to Munn & Co., 361 Broadway, New York.

Canadian patents may now be obtained by the inventors for any of the inventions named in the foregoing list. For terms and further particulars address Munn & Co., 361 Broadway, New York.

KEEP UP WITH THE TIMES.

SAVAGE

Do not buy a rifle until you have examined into the merits of the which is the

TWENTIETH CENTURY ARM.
ABSOLUTELY SAFE.
STRONGEST SHOOTER.

Only Hammerless repeating rifle in the world. Constructed to shoot 6 different cartridges in one rifle.



Adapted for grizzly bears and rabbits. We guarantee every SAVAGE Rifle. .303 and 30-30 Calibres. Write for our handsome new catalogue A.

BAKER & HAMILTON, San Francisco and Sacramento, Cal. Pacific Coast Agents.

SAVAGE ARMS CO., UTICA, N. Y., U. S. A.
Awarded Grand Gold Medal at Paris, beating all competitors.

"HOT BATH IN ONE MINUTE" FOR ONE CENT.

Moses, by the aid of a rod, struck a rock and got cold water. You by the aid of a **Humphrey Crescent Heater** strike a match and get hot water. They require no complicated piping, simply connect with water and gas in your bathroom. **Guaranteed.**

☞ *Write for Booklet.*

HUMPHREY MFG. & PLATING CO., Kalamazoo, Mich.

ASK FOR and INSIST on getting the quick open and quick shut 20th CENTURY UMBRELLA. It will save your gloves, fingers and temper.

20th Century Umbrella Runner.

Pat. Jan. 9, 1900.

Opens with a Push. Closes with a Pull.

A. H. BAMBERGER, 381 Broadway, New York.

ELECTRIC SEWING MACHINE MOTOR.—The instructions and numerous illustrations of details contained in this article will enable any mechanic of average ability to build an efficient motor that will operate a sewing machine. The cost of materials for this machine should not exceed five dollars. See SCIENTIFIC AMERICAN SUPPLEMENT, No. **1210.** Price 10 cents by mail, from this office, and from all newsdealers.

THE Topophone, $25

PREVENTS MARINE DISASTERS IN

FOGS.

See SCI. AM., March 30, 1901, or write for Circular to J. B. COLT CO., Room 1, 21 Barclay St., New York.

AUTOMOBILE STEAM BOILERS

These Boilers are made of fire box steel, which has a tensile strength of 55,000 pounds. A double butt strap seam is used. The bottom end of shell is flanged to take flat head. This flange also takes care of difference in expansion between shell and copper tubes. Each boiler is tested to 600 pounds C. W. P. Can also furnish boilers with seamless cold drawn shell.

FRANK MILNE, - - - EVERETT, MASS.

With regard to

PAN-AMERICAN ACCOMMODATION

HOTEL FORNES

Court & Pearl Sts., Buffalo, N. Y.

newly furnished, fireproof, modern, $1.50 per day and up. Write for our Buffalo Theatre and Exposition Guide.

Fraser & Thompson, Proprietors.

ADDITIONAL CAPITAL SUPPLIED.

Charters Secured in any State. Stocks and Bonds Underwritten or Sold under guarantee and on commission. Good Inventions Marketed. Cash furnished for any good enterprise.

DANIELS & COMPANY, Bankers, 6 Wall Street, New York.
Also London, Philadelphia, Boston, San Francisco.



The.. Improved **BELL ODOMETER**

APPLIED TO YOUR AUTOMOBILE .. OR .. CARRIAGE

will give you the exact distance traveled, and announce each mile passed by the stroke of a bell.

Send for Descriptive Circular S.

S. H. DAVIS & CO.
Cor. Portland & Sudbury Sts., Boston, Mass.



THIS GRINDER

Has no pumps, no valves. No piping required to supply it with water. Always ready for use. Simplest in construction, most efficient in operation.

☞ *Send for Catalogue.*

W. F. & JOHN BARNES CO., 1999 RUBY ST., ROCKFORD, ILL.

UPRIGHT DRILLS



Complete line, ranging from Light Friction Disk Drill to 42" Back Geared Self-Feed. Latest improvements. Up-to-date in every respect.

Established 1872.

½ H. P. GAS ENGINE CASTINGS

Materials and Blue Prints. Write for Catalogue 9. PARSELL & WEED, 129-131 W. 31st Street, New York.

AGENTS.—You can't find a better proposition. Honest business, large profits, advancement. Write, give us a chance to convince you. Lewis & Company, 405 North Third Street, St. Louis, Mo.

AGENTS on salary or commission; $12 daily or $100 per month and expenses, selling our claim file to merchants and physicians. Sayers & Company, D 60, 408 Olive Street, St. Louis, Mo.

SHOE BLACKING.—FORMULAS FOR liquid and solid blacking are given in SUPPLEMENT Nos. **1213** and **1239.** Price 10 cents each. For sale by Munn & Co. and all newsdealers.

LYON & HEALY'S Own Make BRASS BAND

INSTRUMENTS. Indorsed by the great Jules Levy as the best in the world. Big Catalog, 400 illustrations, FREE. Positively the lowest prices on Band Instruments, Uniforms and Supplies of all kinds. Also contains Music and Instructions for New Bands. Lyon & Healy, Manufacturers, 38 Adams st., Chicago.

(Lyon & Healy is the largest music house in the world—Editor.)

ROSE POLYTECHNIC INSTITUTE

A College of Engineering. Mechanical, Electrical, Civil Engineering; Chemical Courses; Architecture. Extensive shops. Modernly equipped laboratories in all departments. Expenses low. 19th year. For catalog, address C. L. MEES, President, Terre Haute, Ind.

"The recognized authority on Wiring and Construction."

STANDARD WIRING

for Electric Light and Power, as adopted by the Fire Underwriters of the United States; by H. C. CUSHING, Jr., A.I.E.E., Electrical Engineer and Inspector; in use by over 36,000 Electrical Engineers, Central Station Managers and Wiremen. Because it is the only book on Wiring and Construction kept strictly up to date. Flexible Leather Cover, pocket size, $1. Sent postpaid upon receipt of price, by

H. C. CUSHING, Jr., 39 Cortlandt Street, New York City

SHORTHAND BY MAIL. Pioneer home cour *Catalogue and First Lesson Free.* Potts Shorthand College, Box 33, Williamsport, Pa.

INVENTORS of Cloth Sponging Machines desiring to place an interest, or to bring out an invention with influential parties may address DANIEL EDWARD RYAN, 68 E. 12th St., New York.

GEARS UNION MODEL SUPPLIES MODEL WORKS CATALOGUE FREE. 193 So. CLARK St. CHICAGO.

RUBBER STAMP MAKING.—THIS article describes a simple method of making rubber stamps with inexpensive apparatus. A thoroughly practical article written by an amateur who has had experience in rubber stamp making. One illustration. Contained in SUPPLEMENT **1110.** Price 10 cents. For sale by Munn & Co. and all newsdealers.

ICE MACHINES, Corliss Engines, Brewers' and Bottlers' Machinery. THE VILTER MFG. CO., 899 Clinton Street, Milwaukee, Wis.

STEEL TYPEWRITER TYPE
TYPE WHEELS, MODELS & EXPERIMENTAL WORK. SMALL MACHINERY NOVELTIES & ETC. NEW YORK STENCIL WORKS 100 NASSAU ST. N.Y.

MODELS & EXPERIMENTAL WORK. Inventions developed. Special Machinery. E. V. BAILLARD, Fox Bldg., Franklin Square, New York.

D'AMOUR & LITTLEDALE MACHINE CO. 130 WORTH ST., NEW YORK. PATTERN AND MODEL MAKERS.

STATLER'S Pan-American HOTEL

The Largest in the World. Send for map of city and Exposition grounds, also folder telling how to SAVE MONEY and secure accommodations.

F. C. STATLER, Prop. Statler's Hotel, at Exposition. Buffalo, N. Y. Statler's Restaurant, Ellicott Sq.

D. L. HOLDEN
REAL ESTATE TRUST BLDG PHILA., PA.
SOLE MANUFACTURER
REGEALED ICE MACHINES
SEE FIRST PAGE SCIENTIFIC AMERICAN SEPT. 2. 1899.

? ? ?

What Do You Want To Buy?

We can tell you where to buy anything you want.
Write us for the addresses of manufacturers in ANY line of business.
Novelties, Special Tools, Machinery, Equipments, New Patent LABOR SAVING DEVICES.

MUNN & CO., Publishers of the SCIENTIFIC AMERICAN, 361 BROADWAY, NEW YORK.

© 1901 SCIENTIFIC AMERICAN, INC.

THOROUGH INSPECTIONS

HARTFORD STEAM BOILER INSPECTION AND INSURANCE CO. HARTFORD, CONN.

AND INSURANCE AGAINST LOSS OR DAMAGE TO PROPERTY AND LOSS OF LIFE AND INJURY TO PERSONS CAUSED BY

STEAM BOILER EXPLOSIONS

J. M. ALLEN, PRESIDENT — W. B. FRANKLIN, VICE PRESIDENT
J. B. PIERCE, SECRETARY — F. B. ALLEN, 2D VICE PRESIDENT
L. B. BRAINERD, TREAS. — L. F. MIDDLEBROOK, ASST SEC'Y

Well Made is Well Paid

There is a superior excellence of design and finish about the

WINTON MOTOR CARRIAGE

that stamps it at once as the Prince of Automobiles. It pays for the scrupulous care taken in every part of its manufacture.

PRICE $1,200.

Strong, safe, sure, and yet simple to operate. As speedy or as slow as you like—you can set the pace without fear of danger. All parts interchangeable. Hydro-Carbon system. Cost ½-cent a mile to run.

THE WINTON MOTOR CARRIAGE CO.,
486 Belden Street, Cleveland, Ohio, U. S. A.
EASTERN DEPOT, 150-152 East 58th Street, New York

ELECTRIC VEHICLES

OF ALL VARIETIES.

STORAGE BATTERIES. MOTORS.

We make a specialty of Delivery Wagons and Busses. ☞ *Write for Catalogue.*

SCOTT AUTOMOBILE CO.,
8927-8939 Olive Street, St. Louis, Mo., U. S. A.

Knox Gasoline Runabout.

WHY SO POPULAR?



Novel and improved engine.
Entire absence of water.
Large carrying space in the body.
Ample power and all changes of speed.
180 miles on the six gallons of fuel carried.
Used in all parts of the country.
Very reliable on account of its extreme simplicity.

Weight 675 Pounds. Price $750. Immediate Delivery.

LIST OF AGENTS.—A. P. UNDERHILL, 33 Stanhope Street, Boston, Mass. SPALDING-BIDWELL CO., 29 West 42d Street, New York City. W. E. ROACH, 821 Arch Street, Philadelphia, Pa. A. G. SPALDING & BROS., 147 Wabash Avenue, Chicago, Ill. SCOTT AUTOMOBILE CO., 3935 Olive Street, St. Louis, Mo. FISHER CYCLE & AUTOMOBILE COMPANY, Delaware Street & Massachusetts Avenue, Indianapolis, Ind.

KNOX AUTOMOBILE CO., SPRINGFIELD, MASS.

GET A RUNNING GEAR and BUILD YOUR OWN AUTOMOBILE



We make two styles, solid rubber or pneumatic tires, complete with springs and wood wheels.

The Brecht Automobile Co., 1205 Cass Av., St. Louis, Mo.

TURN YOUR BIKE into AN AUTOMOBILE

THE BOISSELOT AUTOMOBILE CO.,
101 Beekman St., New York City.

Can tell you how to do this with one of their 1¼ *Actual* Horse Power Gasoline Motors. Under 20 lb. weight. Every motor tested and guaranteed full power. Motors of 2¾ *Actual* Horse Power, air and water cooled, for Voiturettes and Motor Tricycles. 6 *Actual* Horse Power Motors for Automobiles and Express Wagons. Motors for Launches. We also build several types of Automobiles.



A Reliable and Simple FOUR CYLINDER Gasoline Motor

6¼ Brake Horse Power Guaranteed for Marine and Automobile use. Free from vibration, variable speed, starts on quarter turn. Prompt delivery. Additional information cheerfully given.

Catalogue for the asking.

MOTOR VEHICLE POWER CO., 1229 Spring Garden St.
N.Y. Office, 62 Gold St. Philadelphia.



Mistakes in Addition, Office Headache,

and mistakes in carrying forward don't occur where the Comptometer is used. It saves half the time in doing the work and all time looking for errors. Solves with great rapidity and absolute accuracy all arithmetical problems. Why don't you get one? Write for Pamphlet.

FELT & TARRANT MFG CO.
52-56 ILLINOIS ST., CHICAGO.

WALTHAM WATCHES

The Waltham Watch Company was the first company in America to make watches; the first to be organized (half a century ago), and is the first at the present time in the quality and volume of its product.

"The Perfected American Watch", an illustrated book of interesting information about watches, will be sent free upon request.

American Waltham Watch Company,
Waltham, Mass.



DRIVING A PLEASURE when holding your horse with an IMPERIAL BIT, giving 100 per cent more leverage than any other. Any lady can control the most vicious horse. Positive cure for tongue-lolling. Will prevent side pulling and driving on one line. Sent to any address, postpaid, upon receipt of price. In X C plate or imitation rubber, $1. In fine nickel plate, $2.

Imperial Bit and Snap Co., 14th Street, Racine, Wis.



BICYCLE MOTORS
$60.00
Guaranteed best made. Sets of castings with aluminium crank case and blue prints, $10.00.
STEFFEY MFG. CO.,
2720 Brown St., Phila., Pa.

CREST MFG. CO.
CAMBRIDGEPORT, MASS.

3 to 5 H. P. MOTORS



CREST Sparking Plug

Coils Batteries Carburetors



ELECTRIC VICTORIA.

Columbia AUTOMOBILES

Electric Gasolene

IMPROVED 1901 MODELS FOR QUICK DELIVERY

FORTY MILES ON ONE CHARGE OF BATTERIES

Reliability in Service
Simplicity in Operation
Readiness in Action
Cleanliness in Handling

To obtain the leading type of vehicle at moderate cost it will pay you to Write for 1901 Illustrated Catalogue or Call at

ELECTRIC VEHICLE CO., 100 BROADWAY, NEW YORK.

CRACKS IN FLOORS

are unsightly, unclean and unsanitary. GRIPPIN'S WOOD, CRACK AND CREVICE FILLER is the only perfect remedy. A Paste, easily applied, elastic, adhesive, and non-shrinkable. Dirt and moth proof. Cost about ½c. per sq. ft. 5 lbs. will treat an average room. Price 20 cts. per lb. State the kind and condition of wood when ordering, and full instructions will be given. Is also the best filler for open-grained woods.

GRIPPIN MFG. CO., Lock Box L, Newark, New York.
(Inclose stamp for booklet.)

Paint that Pleases

by its permanent beauty and wonderful durability, as well as its "preserving" properties on wood or metal is



DIXON'S SILICA-GRAPHITE PAINT

Lasts four times as long as other paints and always looks well, as it never fades. Non-poisonous, no bad odor, causes no colic or cramps in workmen. Color cards free.

JOSEPH DIXON CRUCIBLE CO.
Jersey City, N. J.

UNION KNIFE & TOOL GRINDER No. 1



SHARPEN-UP!

Acknowledged the Best Light Grinding Machine on the Market. Gear driven. No belts to slip. Easy to run. Cone bearings well fitted. Every Machine Warranted. Designed especially for Bicycle and Repair Shops, Plumbing and Carpenter Shops, and all light grinding. Just the machine for Hotels, Restaurants and Private Homes for grinding knives, etc. Having a speed of 2,000 revolutions and over, buffing and polishing can also be done.

Shipped complete ready to grind.

Price, $6.00.

Buff Wheel, $1.25 extra.
Shipping weight, 25 lbs.

Send for Price List of foot power grinders, also, if interested, for catalog of the largest line in the world of Oil Stones, Scythe Stones, Razor Hones and sharpening stones and material for all purposes.

Booklet, "How to Select and Use Oil Stones," free on application.

THE PIKE M'F'G CO.,
Pike Station, N. H.

EMERY WHEEL USERS

can obtain a formula when used in glue will always make the emery paper stick. Remit $1.00 and I will forward this valuable recipe by return mail. **Your money back** if it does not do the work.

G. WILSON, 1133 Broadway, N. Y.

GAS ENGINE DETAILS.—A VALUABLE and fully illustrated article on this subject is contained in SUPPLEMENT No. 1292. Price 10 cents. For saleby Munn & Co. and all newsdealers.



GENTLEMEN: — The GOODFORM Trousers Hanger is made of fine, specially rolled spring steel, heavily nickel-plated on copper. The parts in contact with the fabric are wide and the edges rounded. It operates automatically. "You press the button," and the keeper does the rest. Sample by mail, 35c.; 3 for $1.00; 6 and a closet loop, $2.00. All express prepaid. **This is what you want if you want the best.**



Sold by Hardware and Furnishing stores, or prepaid for the price. Remit to the maker.

CHICAGO FORM CO., Dept. 76, 124 La Salle St., CHICAGO

FOR MEN OF BRAINS

Cortez CIGARS

—MADE AT KEY WEST—

These Cigars are manufactured under the most favorable climatic conditions and from the mildest blends of Havana tobacco. If we had to pay the imported cigar tax our brands would cost double the money. Send for booklet and particulars.

CORTEZ CIGAR CO., KEY WEST.

"KODAK"

Stands for all that is Best in Photography

To the perfection of Kodak construction, to the perfection of the Kodak mechanism, to the perfection of the Kodak lenses, is due the

Triumph of Kodakery

All Kodaks Load in Daylight with our Transparent Film Cartridges. Several styles use either films or plates. Sixty-four page catalogue, describing them in detail, free at the Kodak dealers or by mail.

EASTMAN KODAK CO.
Rochester, N. Y.

PATENTS PROTECTED

AGAINST INFRINGERS.

PATENT PROTECTED, BY THE PATENT TITLE AND GUARANTEE CO. NEW YORK.

Dealers and Manufacturers of Patented Articles Protected against dangerous litigation at a nominal cost.
Also Copyrights and Trademarks.
Booklet on application.
PATENT TITLE & GUARANTEE CO.
Capital $500,000.00.
Telephone, 5553 Cortlandt.
150 Broadway, New York.

JESSOP'S STEEL

THE VERY BEST FOR TOOLS, SAWS ETC.
WM JESSOP & SONS LTD 91 JOHN ST. NEW YORK

CHARTER ENGINE



USED ANY PLACE BY ANY ONE FOR ANY PURPOSE

FUEL—Gasoline, Gas, Distillate
Stationaries, Portables, Engines and Pumps, Hoisters

Send for Catalogue and Testimonials.
☞ State Your Power Needs

CHARTER GAS ENGINE CO., Box 148, STERLING, ILL.

WATCHES!

No advertisement can properly portray the striking effects produced in our watches. They are illustrated in our

BLUE BOOK showing Ladies' Watches in all metals and exquisite enamels; our

RED BOOK showing Men's and Boys' Watches with up-to-date attractive designs.

Either Blue or Red Book sent on application.

THE NEW ENGLAND WATCH CO.,
37 & 39 Maiden Lane, New York City. 149 State Street, Chicago.
Spreckels Building, San Francisco.

STEWARD'S WONDER

Is the highest class Acetylene Gas Burner. All Lava Tips. A new argand burner $2.50 highest candle power obtainable. Correspondence solicited.
STATE LINE MFG. CO., Chattanooga, Tenn., U. S. A.

RUST PREVENTED ON GUNS TOOLS & CYCLES BY MANNOCITIN
C. H. BESLY & CO. CHICAGO ILL. U.S.A.

Scales All varieties at lowest prices. Best Railroad Track and Wagon or Stock Scales made. Also 1000 useful articles, including Safes, Sewing Machines, Bicycles, Tools, etc. Save Money. Lists Free. CHICAGO SCALE CO., Chicago, Ill.



We Manufacture NOTES, CHECKS, DRAFTS, BILLS OF LADING and other monetary paper absolutely protected against alteration. *Reliable agents wanted.*

A perfect protection for your Bank Account. Write us a letter and we shall be pleased to tell you all about the SECURITY CHECK and furnish you samples. Cost is very little.

The Security Check Co. 45 Lib'rty Street, New York.

© 1901 SCIENTIFIC AMERICAN, INC.